STATE OF MISSOURI

DEPARTMENT OF NATURAL RESOURCES

MISSOURI CLEAN WATER COMMISSION



MISSOURI STATE OPERATING PERMIT

In compliance with the Missouri Clean Water Law, (Chapter 644 R.S. Mo. as amended, hereinafter, the Law), and the Federal Water Pollution Control Act (Public Law 92-500, 92nd Congress) as amended,

Permit No.	MO-0108995
Owner:	Village of Hartsburg
Address:	P.O. Box 37, Hartsburg, MO 65039
Continuing Authority:	Same as above
Address:	Same as above
Facility Name:	Hartsburg Wastewater Treatment Facility
Facility Address:	0.5 miles SE of 2 nd Street & Katy Trail intersection, Hartsburg, MO 65039
Legal Description:	Sec. 8, T45N, R12W, Boone County
UTM Coordinates:	X=560665, Y=4282511
Receiving Stream:	Tributary to Slate Creek (C)
First Classified Stream and ID:	8-20-13 MUDD V1.0 (C) (3960)
USGS Basin & Sub-watershed No.:	(10300102-1302)

is authorized to discharge from the facility described herein, in accordance with the effluent limitations and monitoring requirements as set forth herein:

FACILITY DESCRIPTION

<u>Outfall #001</u> – POTW – SIC #4952 The use or operation of this facility shall be by or under the supervision of a Certified "D" Operator. Two-cell lagoon with aerated primary cell / UV disinfection / sludge retained in lagoon Design population equivalent is 144. Design flow is 14,400 gallons per day. Actual flow is 2,900 gallons per day. Design sludge production is 2.2 dry tons/year.

This permit authorizes only wastewater discharges under the Missouri Clean Water Law and the National Pollutant Discharge Elimination System; it does not apply to other regulated areas. This permit may be appealed in accordance with Section 621.250 RSMo, Section 640.013 RSMo and Section 644.051.6 of the Law.

November 1, 2018 Effective Date

Edward B. Galbraith, Director, Division of Environmental Quality

Chris Wieberg, Director, Water Protection Program

October 31, 2023 Expiration Date

TABLE A-1. INTERIM EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS

The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The interim effluent limitations shall become effective on <u>November 1, 2018</u> and remain in effect through <u>October 31, 2028</u>. Such discharges shall be controlled, limited and monitored by the permittee as specified below:

EFFLUENT PARAMETER(S)	UNITS		-	RIM EFFLUENT MONITORING REQUIREM				
EFFLUENT PARAMETER(5)	UNITS	DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE		
Flow	MGD	*		*	once/quarter***	24 hr. estimate		
Biochemical Oxygen Demand ₅	mg/L		65	45	once/quarter***	grab		
Total Suspended Solids	mg/L		120	80	once/quarter***	grab		
E. coli (Note 1)	#/100mL		1,030	206	once/quarter***	grab		
Ammonia as N	mg/L	*		*	once/quarter***	grab		
Oil & Grease	mg/L	*		*	once/quarter***	grab		
MONITORING REPORTS SHALL BE SUBMI NO DISCHARGE OF FLOATING SOLIDS OR						HERE SHALL BE		
EFFLUENT PARAMETER(S)	UNITS	MINIMUM		MAXIMUM	MEASUREMENT FREQUENCY	SAMPLE TYPE		
pH – Units **	SU	6.5		9.0	once/quarter***	grab		
MONITORING REPORTS SHALL BE SUBMI	ITED <u>QUART</u>	<u>ERLY;</u> THE F	FIRST REPOR	RT IS DUE <u>JA</u>	NUARY 28, 2019.			
EFFLUENT PARAMETER(S)				MONTHLY AVERAGE MINIMUM	MEASUREMENT FREQUENCY	SAMPLE TYPE		
Biochemical Oxygen Demand ₅ – Percent Removal (Note 2)			%	65	once/quarter***	calculated		
Total Suspended Solids – Percent Removal		%	65	once/quarter***	calculated			
MONITORING REPORTS SHALL BE SUBMI	ITED <u>QUART</u>	<u>ERLY;</u> THE F	FIRST REPOR	RT IS DUE <u>JA</u>	NUARY 28, 2019.			

* Monitoring requirement only.

** pH is measured in pH units and is not to be averaged.

*** See table on Page 4 for quarterly sampling requirements

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a geometric mean. The Weekly Average for *E. coli* will be expressed as a geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

Note 2 – Influent sampling is not required when the facility does not discharge effluent during the reporting period. Samples are to be collected prior to any treatment process. Percent removal is calculated by the following formula: [(Influent - Effluent) / Influent] x 100% = Percent Removal. The Monthly Average Minimum Percent removal is to be reported as the average of all daily calculated removal efficiencies. Influent samples are to be collected as a grab sample.

TABLE A-2. FINAL EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS

The permittee is authorized to discharge from outfall(s) with serial number(s) as specified in the application for this permit. The final effluent limitations shall become effective on <u>November 1, 2028</u> and remain in effect until expiration of the permit. Such discharges shall be controlled, limited and monitored by the permittee as specified below:

		FINAL EFF	LUENT LIN	IITATIONS	MONITORING RE	EQUIREMENTS
EFFLUENT PARAMETER(S)	UNITS	DAILY MAXIMUM	WEEKLY AVERAGE	MONTHLY AVERAGE	MEASUREMENT FREQUENCY	SAMPLE TYPE
Flow	MGD	*		*	once/quarter***	24 hr. estimate
Biochemical Oxygen Demand ₅	mg/L		65	45	once/quarter***	grab
Total Suspended Solids	mg/L		120	80	once/quarter***	grab
E. coli (Note 1)	#/100mL		1,030	206	once/quarter***	grab
Ammonia as N (Apr 1 – Sep 30) (Oct 1 – Mar 31)	mg/L	4.3 9.3		1.4 2.8	once/quarter***	grab
Oil & Grease	mg/L	*		*	once/quarter***	grab
MONITORING REPORTS SHALL BE SUBM NO DISCHARGE OF FLOATING SOLIDS OF					NUARY 28, 2029. TI	HERE SHALL BE
EFFLUENT PARAMETER(S)	UNITS	MINIMUM		MAXIMUM	MEASUREMENT FREQUENCY	SAMPLE TYPE
pH – Units **	SU	6.5		9.0	once/quarter***	grab
MONITORING REPORTS SHALL BE SUBM	ITTED QUART	ERLY; THE F	IRST REPOR	T IS DUE <u>JAN</u>	NUARY 28, 2029.	
EFFLUENT PARAMETER(S)			UNITS	MONTHLY AVERAGE MINIMUM	MEASUREMENT FREQUENCY	SAMPLE TYPE
Biochemical Oxygen Demand ₅ – Percent Removal (Note 2)			%	65	once/quarter***	calculated
Total Suspended Solids – Percent Removal		%	65	once/quarter***	calculated	
MONITORING REPORTS SHALL BE SUBM	ITTED <u>QUART</u>	<u>ERLY;</u> THE F	IRST REPOR	RT IS DUE <u>JAN</u>	NUARY 28, 2029.	
* Monitoring requirement only.						

* Monitoring requirement only.

** pH is measured in pH units and is not to be averaged.

*** See table on Page 4 for quarterly sampling requirements

Note 1 - Effluent limitations and monitoring requirements for *E. coli* are applicable only during the recreational season from April 1 through October 31. The Monthly Average Limit for *E. coli* is expressed as a geometric mean. The Weekly Average for *E. coli* will be expressed as a geometric mean if more than one (1) sample is collected during a calendar week (Sunday through Saturday).

Note 2 – Influent sampling is not required when the facility does not discharge effluent during the reporting period. Samples are to be collected prior to any treatment process. Percent removal is calculated by the following formula: [(Influent - Effluent) / Influent] x 100% = Percent Removal. The Monthly Average Minimum Percent removal is to be reported as the average of all daily calculated removal efficiencies. Influent samples are to be collected as a grab sample.

	Quarterly Minimum Sampling Requirements									
Quarter	Months	E. coli	All Other Parameters	Report is Due						
First	January, February, March	Not required to sample.	Sample at least once during any month of the quarter	April 28 th						
Second	April, May, June	Sample at least once during any month of the quarter	Sample at least once during any month of the quarter	July 28 th						
Third	July, August, September	Sample at least once during any month of the quarter	Sample at least once during any month of the quarter	October 28 th						
F 4	October	Sample once during <u>October</u>	Sample at least once during	L Ooth						
Fourth	November & December	Not required to sample.	any month of the quarter	January 28 th						

B. SCHEDULE OF COMPLIANCE

The facility shall attain compliance with final effluent limitations for Ammonia as soon as reasonably achievable or no later than **10 years** of the effective date of this permit.

- 1. Within six months of the effective date of this permit, the permittee shall report progress made in attaining compliance with the final effluent limits.
- 2. The permittee shall submit interim progress reports detailing progress made in attaining compliance with the final effluent limits every 12 months from effective date.
- 3. Within **10 years** of the effective date of this permit, the permittee shall attain compliance with the final effluent limits.

Please submit progress reports to the Missouri Department of Natural Resources via the Electronic Discharge Monitoring Report (eDMR) Submission System.

C. STANDARD CONDITIONS

In addition to specified conditions stated herein, this permit is subject to the attached <u>Parts I, II, & III</u> standard conditions dated <u>August 1, 2014, May 1, 2013, and March 1, 2015</u>, and hereby incorporated as though fully set forth herein.

D. SPECIAL CONDITIONS

1. Electronic Discharge Monitoring Report (eDMR) Submission System.

The permittee shall submit an eDMR Permit Holder and Certifier Registration form within **90 days** of the effective date of this permit. Per 40 CFR Part 127 National Pollutant Discharge Elimination System (NPDES) Electronic Reporting Rule, reporting of effluent limits and monitoring shall be submitted by the permittee via an electronic system to ensure a timely, complete, accurate, and nationally-consistent set of data. Visit <u>http://dnr.mo.gov/pubs/pub2474.pdf</u> to access the Facility Participation Package which contains the eDMR Permit Holder and Certifier Registration form.

Once the permittee is activated in the eDMR system:

- (a) Discharge Monitoring Reporting Requirements. The permittee must electronically submit compliance monitoring data via the eDMR system. In regards to Standard Conditions Part I, Section B, #7, the eDMR system is currently the only Department approved reporting method for this permit.
- (b) Programmatic Reporting Requirements. The following reports (if required by this permit) must be electronically submitted as an attachment to the eDMR system until such a time when the current or a new system is available to allow direct input of the data:
 - (1) Collection System Maintenance Annual Reports;
 - (2) Schedule of Compliance Progress Reports;

D. SPECIAL CONDITIONS (continued)

- (3) Sludge/Biosolids Annual Reports; and
- (4) Any additional report required by the permit excluding bypass reporting.

After such a system has been made available by the Department, required data shall be directly input into the system by the next report due date.

- (c) Other actions. The following shall be submitted electronically after such a system has been made available by the Department:
 - (1) Notices of Intent to discharge (NOIs);
 - (2) Notices of Termination (NOTs); and
 - (3) Bypass reporting, See Special Condition #11 for 24-hr. bypass reporting requirements.
- (d) Electronic Submissions. To access the eDMR system, use the following link in your web browser: <u>https://edmr.dnr.mo.gov/edmr/E2/Shared/Pages/Main/Login.aspx</u>.
- (e) Waivers from Electronic Reporting. The permittee must electronically submit compliance monitoring data and reports unless a waiver is granted by the Department in compliance with 40 CFR Part 127. The permittee may obtain an electronic reporting waiver by first submitting an eDMR Waiver Request Form: <u>http://dnr.mo.gov/forms/780-2692-f.pdf</u>. The Department will either approve or deny this electronic reporting waiver request within 120 calendar days. Only permittees with an approved waiver request may submit monitoring data and reports on paper to the Department for the period that the approved electronic reporting waiver is effective.
- 2. The full implementation of this operating permit, which includes implementation of any applicable schedules of compliance, shall constitute compliance with all applicable federal and state statutes and regulations in accordance with §644.051.16, RSMo, and the Clean Water Act (CWA) section 402(k); however, this permit may be reopened and modified, or alternatively revoked and reissued:
 - (a) To comply with any applicable effluent standard or limitation issued or approved under Sections 301(b)(2)(C) and (D),
 - 304(b)(2), and 307(a)(2) of the CWA, if the effluent standard or limitation so issued or approved:
 - (1) contains different conditions or is otherwise more stringent than any effluent limitation in the permit; or
 - (2) controls any pollutant not limited in the permit.
 - (b) To incorporate an approved pretreatment program pursuant to 40 CFR 403.8(a).
- 3. All outfalls must be clearly marked in the field.
- 4. Permittee will cease discharge by connection to a facility with an area-wide management plan per 10 CSR 20-6.010(3)(B) within 90 days of notice of its availability.
- 5. Report as no-discharge when a discharge does not occur during the report period.
- 6. Changes in existing pollutants or the addition of new pollutants to the treatment facility.

The permittee must provide adequate notice to the Director of the following:

- (a) Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to section 301 or 306 of CWA if it were directly discharging those pollutants; and
- (b) Any substantial change in the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit.
- (c) For purposes of this paragraph, adequate notice shall include information on;
 - (1) the quality and quantity of effluent introduced into the POTW, and
 - (2) any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.
- 7. Reporting of Non-Detects:
 - (a) An analysis conducted by the permittee or their contracted laboratory shall be conducted in such a way that the precision and accuracy of the analyzed result can be enumerated.
 - (b) The permittee shall not report a sample result as "Non-Detect" without also reporting the detection limit of the test. Reporting as "Non Detect" without also including the detection limit will be considered failure to report, which is a violation of this permit.
 - (c) The permittee shall provide the "Non-Detect" sample result using the less than sign and the minimum detection limit (e.g. <10).
 - (d) Where the permit contains a Minimum Level (ML) and the permittee is granted authority in the permit to report zero in lieu of the < ML for a specified parameter (conventional, priority pollutants, metals, etc.), then zero (0) is to be reported for that parameter.
 - (e) See Standard Conditions Part I, Section A, #4 regarding proper detection limits used for sample analysis.
 - (f) When calculating monthly averages, one-half of the method detection limit (MDL) should be used instead of a zero. Where all data are below the MDL, the "<MDL" shall be reported as indicated in item (c).

D. SPECIAL CONDITIONS (continued)

- 8. It is a violation of the Missouri Clean Water Law to fail to pay fees associated with this permit (644.055 RSMo).
- 9. The permittee shall comply with any applicable requirements listed in 10 CSR 20-9. The permittee has been granted approval for an alternative operational monitoring schedule in accordance with 10 CSR 20-9.010(3). This approval is limited to operational monitoring and does not apply to the certified operator requirements of 10 CSR 20-9.020. The applicable operational monitoring parameters and frequencies for this facility are:

Operational Monitoring Parameter	Frequency
Weather Conditions – Ambient Temperature, Cloud Cover, and Precipitation	once per month
Flow – Influent or Effluent	once per month
pH – Primary Cell	once per month
Dissolved Oxygen – Primary Cell	once per month

10. The permittee shall develop and implement a program for maintenance and repair of the collection system. The recommended guidance is the US EPA's Guide for Evaluating Capacity, Management, Operation, And Maintenance (CMOM) Programs at Sanitary Sewer Collection Systems (Document number EPA 305-B-05-002) or the Departments' CMOM Model located at http://dnr.mo.gov/env/wpp/permits/docs/cmom-template.doc. For additional information regarding the Departments' CMOM Model, see the CMOM Plan Model Guidance document at http://dnr.mo.gov/pubs/pub2574.htm.

The permittee shall also submit a report via the Electronic Discharge Monitoring Report (eDMR) Submission System annually, by January 28th, for the previous calendar year. The report shall contain the following information:

- (a) A summary of the efforts to locate and eliminate sources of excessive infiltration and inflow into the collection system serving the facility for the previous year.
- (b) A summary of the general maintenance and repairs to the collection system serving the facility for the previous year.
- (c) A summary of any planned maintenance and repairs to the collection system serving the facility for the upcoming calendar year. This list shall include locations (GPS, 911 address, manhole number, etc.) and actions to be taken.
- 11. Bypasses are not authorized at this facility unless they meet the criteria in 40 CFR 122.41(m). If a bypass occurs, the permittee shall report in accordance to 40 CFR 122.41(m)(3), and with Standard Condition Part I, Section B, subsection 2.b. Bypasses are to be reported to the Northeast Regional Office during normal business hours or by using the online Sanitary Sewer Overflow/Facility Bypass Application located at: http://dnr.mo.gov/modnrcag/ or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. Once an electronic reporting system compliant with 40 CFR Part 127, the National Pollutant Discharge Elimination System (NPDES) Electronic Reporting Rule, is available all bypasses must be reported electronically via the new system. Blending, which is the practice of combining a partially-treated wastewater process stream with a fully-treated wastewater process stream prior to discharge, is not considered a form of bypass. If the permittee wishes to utilize blending, the permittee shall file an application to modify this permit to facilitate the inclusion of appropriate monitoring conditions.
- 12. The facility must be sufficiently secured to restrict entry by children, livestock and unauthorized persons as well as to protect the facility from vandalism.
- 13. At least one gate must be provided to access the wastewater treatment facility and provide for maintenance and mowing. The gate shall remain closed except when temporarily opened by the permittee to access the facility to perform operational monitoring, sampling, maintenance, or mowing. The gates shall also be temporarily opened for inspections by the Department. The gate shall be closed and locked when the facility is not staffed.
- 14. At least one (1) warning sign shall be placed on each side of the facility enclosure in such positions as to be clearly visible from all directions of approach. There shall also be one (1) sign placed for every five hundred feet (500') (150 m) of the perimeter fence. A sign shall also be placed on each gate. Minimum wording shall be SEWAGE TREATMENT FACILITY—KEEP OUT. Signs shall be made of durable materials with characters at least two inches (2") high and shall be securely fastened to the fence, equipment or other suitable locations.
- 15. An Operation and Maintenance (O & M) manual shall be maintained by the permittee and made available to the operator. The O & M manual shall include key operating procedures and a brief summary of the operation of the facility.
- 16. An all-weather access road shall be provided to the treatment facility.

D. SPECIAL CONDITIONS (continued)

- 17. The discharge from the wastewater treatment facility shall be conveyed to the receiving stream via a closed pipe or a paved or riprapped open channel. Sheet or meandering drainage is not acceptable. The outfall sewer shall be protected against the effects of floodwater, ice or other hazards as to reasonably insure its structural stability and freedom from stoppage. The outfall shall be maintained so that a sample of the effluent can be obtained at a point after the final treatment process and before the discharge mixes with the receiving waters.
- 18. A minimum of two (2) feet freeboard must be maintained in each lagoon cell. A lagoon level gauge, which clearly marks the minimum freeboard level, shall be provided in each lagoon cell.
- 19. The berms of the lagoon shall be mowed and kept free of any deep-rooted vegetation, animal dens, or other potential sources of damage to the berms.
- 20. The facility shall ensure that adequate provisions are provided to prevent surface water intrusion into the lagoon and to divert stormwater runoff around the lagoon and protect embankments from erosion.

MISSOURI DEPARTMENT OF NATURAL RESOURCES FACT SHEET FOR THE PURPOSE OF RENEWAL OF MO-0108995 HARTSBURG WWTF

The Federal Water Pollution Control Act ("Clean Water Act" Section 402 Public Law 92-500 as amended) established the National Pollution Discharge Elimination System (NPDES) permit program. This program regulates the discharge of pollutants from point sources into the waters of the United States, and the release of stormwater from certain point sources. All such discharges are unlawful without a permit (Section 301 of the "Clean Water Act"). After a permit is obtained, a discharge not in compliance with all permit terms and conditions is unlawful. Missouri State Operating Permits (MSOPs) are issued by the Director of the Missouri Department of Natural Resources (Department) under an approved program, operating in accordance with federal and state laws (Federal "Clean Water Act" and "Missouri Clean Water Law" Section 644 as amended). MSOPs are issued for a period of <u>five</u> (5) years unless otherwise specified.

As per [40 CFR Part 124.8(a)] and [10 CSR 20-6.020(1)(A)2.] a Factsheet shall be prepared to give pertinent information regarding the applicable regulations, rationale for the development of effluent limitations and conditions, and the public participation process for the Missouri State Operating Permit (operating permit) listed below.

A Factsheet is not an enforceable part of an operating permit.

This Factsheet is for a Minor Municipal.

Part I – Facility Information

Facility Type: POTW - SIC #4952

Facility Description:

Two-cell lagoon / primary cell aerated / UV disinfection / sludge retained in lagoon

Have any changes occurred at this facility or in the receiving water body that effects effluent limit derivation? \Box - Yes;

🛛 - No.

Application Date:	12/16/2010
Expiration Date:	08/10/2011

OUTFALL(S) TABLE:

OUTFALL	DESIGN FLOW (CFS)	TREATMENT LEVEL	EFFLUENT TYPE
#001	0.02	Equivalent to Secondary	Domestic

Facility Performance History:

The facility failed to meet effluent limits for Biochemical Oxygen Demand (BOD) on the April 2013, April 2014, February 2015, and March 2017 Discharge Monitoring Reports (DMRs). The facility failed to meet effluent limits Total Suspended Solids (TSS) on the March 2017 DMR. The facility failed to meet effluent limits for Fecal Coliform on the August, September, and November 2011, April, May, June, July, August, September, and October 2012, April, May, June, July, August, September, and October 2013, and May, June, July, and August 2014, July 2016, and May 2017 DMRs. The facility failed to submit the July 2017 DMR. This facility was last inspected on October 24, 2013. The inspection showed the following unsatisfactory features; and failure to meet final limits for Fecal Coliform and Biochemical Oxygen Demand.

Comments:

Changes in this permit include the addition of effluent limits for Ammonia, monitoring requirements for Oil & Grease and the removal of Temperature. See Part VI of the Fact Sheet for further information regarding the addition and removal of effluent parameters. Special conditions were updated to include the addition of inflow and infiltration reporting requirements, reporting of Non-detects, and bypass reporting requirements.

Part II – Operator Certification Requirements

 \boxtimes - This facility is required to have a certified operator.

As per [10 CSR 20-6.010(8) Terms and Conditions of a Permit], the permittee shall operate and maintain facilities to comply with the Missouri Clean Water Law and applicable permit conditions and regulations. Operators or supervisors of operations at regulated wastewater treatment facilities shall be certified in accordance with [10 CSR 20-9.020(2)] and any other applicable state law or regulation. As per [10 CSR 20-9.020(2)(A)], requirements for operation by certified personnel shall apply to all wastewater treatment systems, if applicable, as listed below:

State agency
 - Private Sewer Company regulated by the Public Service Commission
 - Public Water Supply Districts

Each of the above entities are only applicable if they have a Population Equivalent greater than two hundred (200) or fifty (50) or more service connections.

This facility currently requires an operator with a <u>C</u> Certification Level. Please see **Appendix - Classification Worksheet**. Modifications made to the wastewater treatment facility may cause the classification to be modified.

Operator's Name:	Dwayne F. Cooksey
Certification Number:	1249
Certification Level:	А

The listing of the operator above only signifies that staff drafting this operating permit have reviewed appropriate Department records and determined that the name listed on the operating permit application has the correct and applicable Certification Level.

- This facility is not required to have a certified operator.

Part III- Operational Monitoring

- As per [10 CSR 20-9.010(4))], the facility is not required to conduct operational monitoring.

 \boxtimes - As per [10 CSR 20-9.010(4))], the facility is required to conduct operational monitoring.

- ☑ The facility has a Department approved modification to the Operational Control Testing requirements.
 - The Department has approved alternative monitoring frequencies for the requirements in 10 CSR 20-9.010(5)(A) for the facility.

Part IV – Receiving Stream Information

RECEIVING STREAM(S) TABLE: OUTFALL #001

WATER-BODY NAME	CLASS	WBID	DESIGNATED USES*	12-DIGIT HUC	DISTANCE TO CLASSIFIED SEGMENT (MI)
Tributary to Slate Creek (8-20-13 MUDD V1.0)	С	3960	AQL, WBC- B, SCR, HHP, IRR, LWW	10300102- 1302	0

*As per 10 CSR 20-7.031 Missouri Water Quality Standards, the department defines the Clean Water Commission's water quality objectives in terms of "water uses to be maintained and the criteria to protect those uses." The receiving stream and 1st classified receiving stream's beneficial water uses to be maintained are in the receiving stream table in accordance with [10 CSR 20-7.031(1)(C)].

Uses which may be found in the receiving streams table, above:

10 CSR 20-7.031(1)(C)1.:

AQL = Protection of aquatic life (Current narrative use(s) are defined to ensure the protection and propagation of fish shellfish and wildlife, which is further subcategorized as: WWH = Warm Water Habitat; CDF = Cold-water fishery (Current narrative use is cold-water habitat.); CLF = Cool-water fishery (Current narrative use is cool-water habitat.); EAH = Ephemeral Aquatic Habitat; MAH = Modified Aquatic Habitat; LAH = Limited Aquatic Habitat. This permit uses AQL effluent limitations in 10 CSR 20-7.031 Table A for all habitat designations unless otherwise specified.)

10 CSR 20-7.031(1)(C)2.: Recreation in and on the water
 WBC = Whole Body Contact recreation where the entire body is capable of being submerged;
 WBC-A = Whole body contact recreation that supports swimming uses and has public access;

WBC-B = Whole body contact recreation that supports swimming;

SCR = Secondary Contact Recreation (like fishing, wading, and boating).

10 CSR 20-7.031(1)(C)3. to 7.:

HHP (formerly HHF) = Human Health Protection as it relates to the consumption of fish;

IRR = Irrigation for use on crops utilized for human or livestock consumption;

LWW = Livestock and wildlife watering (Current narrative use is defined as LWP = Livestock and Wildlife Protection); **DWS** = Drinking Water Supply;

IND = Industrial water supply

10 CSR 20-7.031(1)(C)8-11.: Wetlands (10 CSR 20-7.031 Table A currently does not have corresponding habitat use criteria for these defined uses)

WSA = Storm- and flood-water storage and attenuation; WHP = Habitat for resident and migratory wildlife species; WRC = Recreational, cultural, educational, scientific, and natural aesthetic values and uses; WHC = Hydrologic cycle maintenance.

10 CSR 20-7.031(6): **GRW** = Groundwater

RECEIVING STREAM(S) LOW-FLOW VALUES:

$\mathbf{P}_{\mathbf{C}} \in \mathbf{P}_{\mathbf{D}} \cup (\mathbf{C} \in \mathbf{P}_{\mathbf{D}} \cup \mathbf{D})$	LOW-FLOW VALUES (CFS)					
RECEIVING STREAM (C, E, P, P1)	1Q10	7Q10	30Q10			
Tributary to Slate Creek (8-20-13 MUDD V1.0) (C)	0	0	0			

MIXING CONSIDERATIONS

MIXING CONSIDERATIONS TABLE:

	MIXING ZONE (CFS) ZONE OF INITIAL DILUTION (CFS) [10 CSR 20-7.031(5)(A)4.B.(I)(a)] [10 CSR 20-7.031(5)(A)4.B(I)(b)]				
1Q10	7Q10	30Q10	1Q10	7Q10	30Q10
0	0	0	0	0	N/A

RECEIVING STREAM MONITORING REQUIREMENTS:

No receiving water monitoring requirements recommended at this time.

Receiving Water Body's Water Quality

No stream surveys have been conducted for this receiving stream.

Part V – Rationale and Derivation of Effluent Limitations & Permit Conditions

ALTERNATIVE EVALUATIONS FOR NEW FACILITIES:

As per [10 CSR 20-7.015(4)(A)], discharges to losing streams shall be permitted only after other alternatives including land application, discharges to a gaining stream and connection to a regional wastewater treatment facility have been evaluated and determined to be unacceptable for environmental and/or economic reasons.

 \Box - The facility discharges to a Losing Stream as defined by [10 CSR 20-2.010(36)] & [10 CSR 20-7.031(1)(N)], or is an existing facility, and has submitted an alternative evaluation.

 \square - The facility does not discharge to a Losing Stream as defined by [10 CSR 20-2.010(36)] & [10 CSR 20-7.031(1)(N)], or is an existing facility.

ANTI-BACKSLIDING:

A provision in the Federal Regulations [CWA §303(d)(4); CWA §402(o); 40 CFR Part 122.44(l)] that requires a reissued permit to be as stringent as the previous permit with some exceptions.

 \boxtimes - Limitations in this operating permit for the reissuance of this permit conform to the anti-backsliding provisions of Section 402(o) of the Clean Water Act, and 40 CFR Part 122.44.

 \boxtimes - Information is available which was not available at the time of permit issuance (other than revised regulations, guidance, or test methods) and which would have justified the application of a less stringent effluent limitation at the time of permit issuance.

• Temperature was removed as the permit writer did not observe a potential to violate the Water Quality Standards.

 \square - The Department determines that technical mistakes or mistaken interpretations of law were made in issuing the permit under section 402(a)(1)(b).

• <u>General Criteria</u>. The previous permit contained a special condition which described a specific set of prohibitions related to general criteria found in 10 CSR 20-7.031(4). In order to comply with 40 CFR 122.44(d)(1), the permit writer has conducted reasonable potential determinations for each general criterion and established numeric effluent limitations where reasonable potential exists. While the removal of the previous permit special condition creates the appearance of backsliding, since this permit establishes numeric limitations where reasonable potential to cause or contribute to an excursion of the general criteria exists the permit maintains sufficient effluent limitations and monitoring requirements in order to protect water quality, this permit is equally protective as compared to the previous permit. Therefore, given this new information, and the fact that the previous permit special condition was not consistent with 40 CFR 122.44(d)(1), an error occurred in the establishment of the general criteria as a special condition for more information regarding the reasonable potential determinations for each general criterion related to this facility.

ANTIDEGRADATION:

In accordance with Missouri's Water Quality Standard [10 CSR 20-7.031(3)], for domestic wastewater discharge with new, altered, or expanding discharges, the Department is to document by means of Antidegradation Review that the use of a water body's available assimilative capacity is justified. In accordance with Missouri's water quality regulations for antidegradation [10 CSR 20-7.031(3)], degradation may be justified by documenting the socio-economic importance of a discharge after determining the necessity of the discharge. Facilities must submit the antidegradation review request to the department prior to establishing, altering, or expanding discharges. See http://dnr.mo.gov/env/wpp/permits/antideg-implementation.htm

 \square - No degradation proposed and no further review necessary. Facility did not apply for authorization to increase pollutant loading or to add additional pollutants to their discharge.

- This permit contains new and/or expanded discharge, please see APPENDIX FOR ANTIDEGRADATION ANALYSIS.

AREA-WIDE WASTE TREATMENT MANAGEMENT & CONTINUING AUTHORITY:

As per [10 CSR 20-6.010(3)(B)], ... An applicant may utilize a lower preference continuing authority by submitting, as part of the application, a statement waiving preferential status from each existing higher preference authority, providing the waiver does not conflict with any area-wide management plan approved under section 208 of the Federal Clean Water Act or any other regional sewage service and treatment plan approved for higher preference authority by the Department.

BIOSOLIDS & SEWAGE SLUDGE:

Biosolids are solid materials resulting from domestic wastewater treatment that meet federal and state criteria for beneficial uses (i.e. fertilizer). Sewage sludge is solids, semi-solids, or liquid residue generated during the treatment of domestic sewage in a treatment works; including but not limited to, domestic septage; scum or solids removed in primary, secondary, or advanced wastewater treatment process; and a material derived from sewage sludge. Sewage sludge does not include ash generated during the firing of sewage sludge in a sewage sludge incinerator or grit and screening generated during preliminary treatment of domestic sewage in a treatment works. Additional information regarding biosolids and sludge is located at the following web address: http://extension.missouri.edu/main/DisplayCategory.aspx?C=74, items WQ422 through WQ449.

- Permittee has and a Department approved biosolids management plan, and is authorized to land applies biosolids in accordance with Standard Conditions III.

 \square - Permittee is not authorized to land apply biosolids. Sludge is stored in the lagoon. The permittee must submit a sludge management plan for approval that details removal and disposal plans when sludge is to be removed from lagoons.

COMPLIANCE AND ENFORCEMENT:

Enforcement is the action taken by the Water Protection Program (WPP) to bring an entity into compliance with the Missouri Clean Water Law, its implementing regulations, and/or any terms and conditions of an operating permit. The primary purpose of the enforcement activity in the WPP is to resolve violations and return the entity to compliance.

- The facility is currently under enforcement action.

 \boxtimes - The facility is not currently under Water Protection Program enforcement action.

ELECTRONIC DISCHARGE MONITORING REPORT (EDMR) SUBMISSION SYSTEM:

The U.S. Environmental Protection Agency (EPA) promulgated a final rule on October 22, 2015, to modernize Clean Water Act reporting for municipalities, industries, and other facilities by converting to an electronic data reporting system. This final rule requires regulated entities and state and federal regulators to use information technology to electronically report data required by the National Pollutant Discharge Elimination System (NPDES) permit program instead of filing paper reports. To comply with the federal rule, the Department is requiring all permittees to begin submitting discharge monitoring data and reports online. In an effort to aid facilities in the reporting of applicable information electronically, the Department has created several new forms including operational control monitoring forms and an I&I location and reduction form. These forms are for optional use and can be found on the Department's website at the following locations:

Operational Monitoring Lagoon: <u>http://dnr.mo.gov/forms/780-2801-f.pdf</u> Operational Monitoring Mechanical: <u>http://dnr.mo.gov/forms/780-2800-f.pdf</u> I&I Report: <u>http://dnr.mo.gov/forms/780-2690-f.pdf</u>

Per 40 CFR 127.15 and 127.24, permitted facilities may request a temporary waiver for up to 5 years or a permanent waiver from electronic reporting from the Department. To obtain an electronic reporting waiver, a permittee must first submit an eDMR Waiver Request Form: <u>http://dnr.mo.gov/forms/780-2692-f.pdf</u>. A request must be made for each facility. If more than one facility is owned or operated by a single entity, then the entity must submit a separate request for each facility based on its specific circumstances. An approved waiver is non-transferable.

The Department must review and notify the facility within 120 calendar days of receipt if the waiver request has been approved or rejected [40 CFR 124.27(a)]. During the Department review period as well as after a waiver is granted, the facility must continue submitting a hard-copy of any reports required by their permit. The Department will enter data submitted in hard-copy from those facilities allowed to do so and electronically submit the data to the EPA on behalf of the facility.

- The permittee/facility is currently using the eDMR data reporting system.

 \square - The permittee/facility is not currently using the eDMR data reporting system. The permittee shall submit an eDMR Permit Holder and Certifier Registration form within **90 days** of the effective date of this permit.

- The facility has obtained a Department approved waiver from reporting electronically.

PRETREATMENT PROGRAM:

The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to or in lieu of discharging or otherwise introducing such pollutants into a Publicly Owned Treatment Works [40 CFR Part 403.3(q)].

- This permittee has an approved pretreatment program in accordance with the requirements of [40 CFR Part 403] and [10 CSR 20-6.100] and is expected to implement and enforce its approved program.

☑ - The permittee, at this time, is not required to have a Pretreatment Program or does not have an approved pretreatment program.

REASONABLE POTENTIAL ANALYSIS (RPA):

Federal regulation [40 CFR Part 122.44(d)(1)(i)] requires effluent limitations for all pollutants that are or may be discharged at a level that will cause or have the reasonable potential to cause or contribute to an in-stream excursion above narrative or numeric water quality standard.

In accordance with [40 CFR Part 122.44(d)(1)(iii)] if the permit writer determines that any given pollutant has the reasonable potential to cause, or contribute to an in-stream excursion above the WQS, the permit must contain effluent limits for that pollutant.

□ - A RPA was conducted on appropriate parameters. Please see APPENDIX – RPA RESULTS.

- A RPA was not conducted for this facility.

REMOVAL EFFICIENCY:

Removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD₅) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals.

- Secondary Treatment is 85% removal [40 CFR Part 133.102(a)(3) & (b)(3)].

⊠ - Equivalent to Secondary Treatment is 65% removal [40 CFR Part 133.105(a)(3) & (b)(3)].

SANITARY SEWER OVERFLOWS (SSO) AND INFLOW AND INFILTRATION (I&I):

Sanitary Sewer Overflows (SSOs) are defined as untreated sewage releases and are considered bypassing under state regulation [10 CSR 20-2.010(11)] and should not be confused with the federal definition of bypass. SSOs result from a variety of causes including blockages, line breaks, and sewer defects that can either allow wastewater to backup within the collection system during dry weather conditions or allow excess stormwater and groundwater to enter and overload the collection system during wet weather conditions. SSOs can also result from lapses in sewer system operation and maintenance, inadequate sewer design and construction, power failures, and vandalism. SSOs include overflows out of manholes, cleanouts, broken pipes, and other into waters of the state and onto city streets, sidewalks, and other terrestrial locations.

Inflow and Infiltration (I&I) is defined as unwanted intrusion of stormwater or groundwater into a collection system. This can occur from points of direct connection such as sump pumps, roof drain downspouts, foundation drains, and storm drain cross-connections or through cracks, holes, joint failures, faulty line connections, damaged manholes, and other openings in the collection system itself. I&I results from a variety of causes including line breaks, improperly sealed connections, cracks caused by soil erosion/settling, penetration of vegetative roots, and other sewer defects. In addition, excess stormwater and groundwater entering the collection system from line breaks and sewer defects have the potential to negatively impact the treatment facility.

Missouri RSMo §644.026.1.(13) mandates that the Department issue permits for discharges of water contaminants into the waters of this state, and also for the operation of sewer systems. Such permit conditions shall ensure compliance with all requirements as established by sections 644.006 to 644.141. Standard Conditions Part I, referenced in the permit, contains provisions requiring proper operation and maintenance of all facilities and systems of treatment and control. Missouri RSMo §644.026.1.(15) instructs the Department to require proper maintenance and operation of treatment facilities and sewer systems and proper disposal of residual waste from all such facilities. To ensure that public health and the environment are protected, any noncompliance which may endanger public health or the environment must be reported to the Department within 24 hours of the time the permittee becomes aware of the noncompliance. Standard Conditions Part I, referenced in the permit, contains the reporting requirements for the permittee when bypasses and upsets occur. The permit requires that the permittee submit an annual report to the Department for the previous calendar year that contains a summary of efforts taken by the permittee to locate and eliminate sources of excess I & I, a summary of general maintenance and repairs to the collection system, and a summary of any planned maintenance and repairs to the collection system.

☑ - At this time, the Department recommends the US EPA's Guide for Evaluating Capacity, Management, Operation and Maintenance (CMOM) Programs At Sanitary Sewer Collection Systems (Document # EPA 305-B-05-002) or the Departments' CMOM Model located at <u>http://dnr.mo.gov/env/wpp/permits/docs/cmom-template.doc</u>. For additional information regarding the Departments' CMOM Model, see the CMOM Plan Model Guidance document at <u>http://dnr.mo.gov/pubs/pub2574.htm</u>. The CMOM identifies some of the criteria used to evaluate a collection system's management, operation, and maintenance and was intended for use by the EPA, state, regulated community, and/or third party entities. The CMOM is applicable to small, medium, and large systems; both public and privately owned; and both regional and satellite collection systems. The CMOM does not substitute for the Clean Water Act, the Missouri Clean Water Law, and both federal and state regulations, as it is not a regulation.

- This facility is not required to develop or implement a program for maintenance and repair of the collection system; however, it is a violation of Missouri State Environmental Laws and Regulations to allow untreated wastewater to discharge to waters of the state.

SCHEDULE OF COMPLIANCE (SOC):

Per 644.051.4 RSMo, a permit may be issued with a Schedule of Compliance (SOC) to provide time for a facility to come into compliance with new state or federal effluent regulations, water quality standards, or other requirements. Such a schedule is not allowed if the facility is already in compliance with the new requirement, or if prohibited by other statute or regulation. A SOC includes an enforceable sequence of interim requirements (actions, operations, or milestone events) leading to compliance with the Missouri Clean Water Law, its implementing regulations, and/or the terms and conditions of an operating permit. *See also* Section 502(17) of the Clean Water Act, and 40 CFR §122.2. For new effluent limitations, the permit includes interim monitoring for the specific parameter to demonstrate the facility is not already in compliance with the new requirement. Per 40 CFR § 122.47(a)(1) and 10 CSR 20-7.031(11), compliance must occur as soon as possible. If the permit provides a schedule for meeting new water quality based effluent limits, a SOC must include an enforceable, final effluent limitation in the permit even if the SOC extends beyond the life of the permit.

A SOC is not allowed:

- For effluent limitations based on technology-based standards established in accordance with federal requirements, if the deadline for compliance established in federal regulations has passed. 40 CFR § 125.3.
- For a newly constructed facility in most cases. Newly constructed facilities must meet applicable effluent limitations when discharge begins, because the facility has installed the appropriate control technology as specified in a permit or antidegradation review. A SOC is allowed for a new water quality based effluent limit that was not included in a previously public noticed permit or antidegradation review, which may occur if a regulation changes during construction.
- To develop a TMDL, UAA, or other study associated with development of a site specific criterion. A facility is not prohibited from conducting these activities, but a SOC may not be granted for conducting these activities.

In order to provide guidance to Permit Writers in developing SOCs, and attain a greater level of consistency, on April 9, 2015 the Department issued an updated policy on development of SOCs. This policy provides guidance to Permit Writers on the standard time frames for schedules for common activities, and guidance on factors that may modify the length of the schedule such as a Cost Analysis for Compliance.

 \square - The time given for effluent limitations of this permit listed under Interim Effluent Limitation and Final Effluent Limitations were established in accordance with [10 CSR 20-7.031(11)]. The facility has been given a schedule of compliance to meet final effluent limits for Ammonia. The ten year schedule of compliance allowed for this facility should provide adequate time to evaluate operations, obtain an engineering report, hold a bond election, obtain a construction permit and implement upgrades required to meet effluent limits. Due to the low to medium economic burden on this community of the cost of compliance and associated difficulty in raising the necessary funding, the schedule has been established at 10 years in accordance with the Department's "Schedule of Compliance, Policy for Staff Drafting Operating Permits". Please see the Cost Analysis for Compliance attached as an appendix to the permit for further detail on how the socio-economic status of the community has impacted this SOC.

- This permit does not contain a SOC.

STORMWATER POLLUTION PREVENTION PLAN (SWPPP):

In accordance with 40 CFR 122.44(k) *Best Management Practices (BMPs)* to control or abate the discharge of pollutants when: (1) Authorized under section 304(e) of the Clean Water Act (CWA) for the control of toxic pollutants and hazardous substances from ancillary industrial activities: (2) Authorized under section 402(p) of the CWA for the control of stormwater discharges; (3) Numeric effluent limitations are infeasible; or (4) the practices are reasonably necessary to achieve effluent limitations and standards or to carry out the purposes and intent of the CWA.

□ - 10 CSR 20-6.200 and 40 CFR 122.26 includes treatment works treating domestic sewage or any other sewage sludge or wastewater treatment device or system, used in the storage treatment, recycling, and reclamation of municipal or domestic sewage, including land dedicated to the disposal of sewage sludge that is located within the confines of the facility, with a design flow of 1.0 mgd or more, or are required to have an approved pretreatment program under 40 CFR part 403, as an industrial activity in which permit coverage is required.

 \boxtimes - At this time, the permittee is not required to develop and implement a SWPPP.

VARIANCE:

As per the Missouri Clean Water Law § 644.061.4, variances shall be granted for such period of time and under such terms and conditions as shall be specified by the commission in its order. The variance may be extended by affirmative action of the commission. In no event shall the variance be granted for a period of time greater than is reasonably necessary for complying with the Missouri Clean Water Law §§644.006 to 644.141 or any standard, rule or regulation promulgated pursuant to Missouri Clean Water Law §§644.006 to 644.141.

- This operating permit is drafted under premises of a petition for variance.

 \boxtimes - This operating permit is not drafted under premises of a petition for variance.

WASTELOAD ALLOCATIONS (WLA) FOR LIMITS:

As per [10 CSR 20-2.010(78)], the amount of pollutant each discharger is allowed by the Department to release into a given stream after the Department has determined total amount of pollutant that may be discharged into that stream without endangering its water quality.

 \boxtimes - Wasteload allocations were calculated where applicable using water quality criteria or water quality model results and the dilution equation below:

$$Ce = \frac{(Qe + Qs)C - (Qs \times Cs)}{(Qe)} \quad (EPA/505/2-90-001, Section 4.5.5)$$

Where C = downstream concentration Cs = upstream concentration Qs = upstream flow Ce = effluent concentration Qe = effluent flow

Chronic wasteload allocations were determined using applicable chronic water quality criteria (CCC: criteria continuous concentration) and stream volume of flow at the edge of the mixing zone (MZ). Acute wasteload allocations were determined using applicable water quality criteria (CMC: criteria maximum concentration) and stream volume of flow at the edge of the zone of initial dilution (ZID).

Water quality based maximum daily and average monthly effluent limitations were calculated using methods and procedures outlined in USEPA's "Technical Support Document For Water Quality-based Toxics Control" (EPA/505/2-90-001).

Number of Samples "n":

Additionally, in accordance with the TSD for water quality-based permitting, effluent quality is determined by the underlying distribution of daily values, which is determined by the Long Term Average (LTA) associated with a particular Wasteload Allocation (WLA) and by the Coefficient of Variation (CV) of the effluent concentrations. Increasing or decreasing the monitoring frequency does not affect this underlying distribution or treatment performance, which should be, at a minimum, be targeted to comply with the values dictated by the WLA. Therefore, it is recommended that the actual planned frequency of monitoring normally be used to determine the value of "n" for calculating the AML. However, in situations where monitoring frequency is once per month or less, a higher value for "n" must be assumed for AML derivation purposes. Thus, the statistical procedure being employed using an assumed number of samples is "n = 4" at a minimum. For Total Ammonia as Nitrogen, "n = 30" is used

- Wasteload allocations were not calculated.

WLA MODELING:

There are two general types of effluent limitations, technology-based effluent limits (TBELs) and water quality based effluent limits (WQBELs). If TBELs do not provide adequate protection for the receiving waters, then WQBEL must be used.

- A WLA study including model was submitted to the Department.

⊠ - A WLA study was either not submitted or determined not applicable by Department staff.

WATER QUALITY STANDARDS:

Per [10 CSR 20-7.031(4)], General Criteria shall be applicable to all waters of the state at all times including mixing zones. Additionally, [40 CFR 122.44(d)(1)] directs the Department to establish in each NPDES permit to include conditions to achieve water quality established under Section 303 of the Clean Water Act, including State narrative criteria for water quality.

WHOLE EFFLUENT TOXICITY (WET) TEST:

- The permittee is required to conduct WET test for this facility.

 \boxtimes - At this time, the permittee is not required to conduct WET test for this facility.

40 CFR 122.41(M) - BYPASSES:

The federal Clean Water Act (CWA), Section 402 prohibits wastewater dischargers from "bypassing" untreated or partially treated sewage (wastewater) beyond the headworks. A bypass is defined as an intentional diversion of waste streams from any portion of a treatment facility, [40 CFR 122.41(m)(1)(i)]. Additionally, Missouri regulation 10 CSR 20-7.015(9)(G) states a bypass means the intentional diversion of waste streams from any portion of a treatment facility, except in the case of blending, to waters of the state. Only under exceptional and specified limitations do the federal regulations allow for a facility to bypass some or all of the flow from its treatment process. Bypasses are prohibited by the CWA unless a permittee can meet all of the criteria listed in 40 CFR 122.41(m)(4)(i)(A), (B), & (C). Any bypasses from this facility are subject to the reporting required in 40 CFR 122.41(l)(6) and per Missouri's Standard Conditions I, Section B, part 2.b. Additionally, Anticipated Bypasses include bypasses from peak flow basins or similar devices designed for peak wet weather flows.

- Bypasses occur or have occurred at this facility.

 \boxtimes - This facility does not anticipate bypassing.

303(d) LIST & TOTAL MAXIMUM DAILY LOAD (TMDL):

Section 303(d) of the federal Clean Water Act requires that each state identify waters that are not meeting water quality standards and for which adequate water pollution controls have not been required. Water quality standards protect such beneficial uses of water as whole body contact (such as swimming), maintaining fish and other aquatic life, and providing drinking water for people, livestock and wildlife. The 303(d) list helps state and federal agencies keep track of waters that are impaired but not addressed by normal water pollution control programs.

A TMDL is a calculation of the maximum amount of a given pollutant that a body of water can absorb before its water quality is affected. If a water body is determined to be impaired as listed on the 303(d) list, then a watershed management plan will be developed that shall include the TMDL calculation

 \boxtimes - This facility does not discharge to a 303(d) listed stream.

Part VII – Effluent Limits Determination

APPLICABLE DESIGNATIONS OF WATERS OF THE STATE:

As per Missouri's Effluent Regulations [10 CSR 20-7.015], the waters of the state are divided into the below listed seven (7) categories. Each category lists effluent limitations for specific parameters, which are presented in each outfall's Effluent Limitation Table and further discussed in the Derivation & Discussion of Limits section.

All Other Waters [10 CSR 20-7.015(8)]

Missouri or Mississippi River [10 CSR 20-7.015(2)] Subsurface Water [10 CSR 20-7.015(7)]

Lake or Reservoir [10 CSR 20-7.015(3)]

Losing [10 CSR 20-7.015(4)]

Metropolitan No-Discharge [10 CSR 20-7.015(5)]

OUTFALL #001 - MAIN FACILITY OUTFALL

Effluent limitations derived and established in the below Effluent Limitations Table are based on current operations of the facility. Future permit action due to facility modification may contain new operating permit terms and conditions that supersede the terms and conditions, including effluent limitations, of this operating permit.

EFFLUENT LIMITATIONS TABLE:

$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	PARAMETER	Unit	Basis for Limits	Daily Maximum	Weekly Average	Monthly Average	Previous Permit Limit	Sampling Frequency	Reporting Frequency	Sample Type ****
TSSmg/L112080120/801/quarterquarterly0Escherichia coli **#/100mL1, 31,030206Fecal 1000/ 4001/quarterquarterly0Ammonia as N (Interim)mg/L2, 3****/*1/quarterquarterly0Ammonia as N (Apr 1 – Sep 30) (Final)mg/L2, 34.31.4*/*1/quarterquarterly0Ammonia as N (Oct 1 – Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterly0Ammonia as N (Oct 1 – Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterly0Ammonia as N (Oct 1 – Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterly0Ammonia as N (Oct 1 – Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterly0Oil & Greasemg/L8*******1/quarterquarterly0PARAMETERUnitBasis for LimitsMinimumMaximumPrevious Permit LimitSampling FrequencyReporting FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan FrequencySan Frequ	Flow	MGD	1	*		*	*/*	1/quarter	quarterly	Е
Escherichia coli **#/100mL1, 31,030206Fecal 1000/ 4001/quarterquarterlyQuarterlyAmmonia as N (Interim)mg/L2, 3****/*1/quarterquarterlyQuarterlyAmmonia as N (Apr 1 -Sep 30) (Final)mg/L2, 34.31.4*/*1/quarterquarterlyQuarterlyAmmonia as N (Oct 1 - Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterlyQuarterlyOil & Greasemg/L8*****1/quarterquarterlyQuarterlyPARAMETERUnitBasis for LimitsMinimumMaximumPrevious Permit LimitSampling FrequencyReporting FrequencySan <td>BOD₅</td> <td>mg/L</td> <td>1</td> <td></td> <td>65</td> <td>45</td> <td>65/45</td> <td>1/quarter</td> <td>quarterly</td> <td>G</td>	BOD ₅	mg/L	1		65	45	65/45	1/quarter	quarterly	G
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	TSS	mg/L	1		120	80	120/80	1/quarter	quarterly	G
Ammonia as N (merini)ing/L2, 34.31.47i/quarterquarterlyQuarterlyAmmonia as N (Apr 1 - Sep 30) (Final)mg/L2, 34.31.4*/*1/quarterquarterlyQuarterlyAmmonia as N (Oct 1 - Mar 31) (Final)mg/L2, 39.32.8*/*1/quarterquarterlyQuarterlyOil & Greasemg/L8******1/quarterquarterlyQuarterlyOil & Greasemg/L8***see1/quarterquarterlyQuarterlyPARAMETERUnitBasis for 	Escherichia coli **	#/100mL	1, 3		1,030	206	1000/	1/quarter	quarterly	G
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	Ammonia as N (Interim)	mg/L	2, 3	*		*	*/*	1/quarter	quarterly	G
(Final)mg/L2, 39.32.8*/*1/quarterquarterlyQuarterlyOil & Greasemg/L8******1/quarterquarterlyQuarterlyPARAMETERUnitBasis for LimitsMinimumMaximumPrevious Permit LimitSampling FrequencyReporting FrequencySan TyPHSU16.59.0 \geq 6.01/quarterquarterlyQuarterlyPARAMETERUnitBasis for LimitsMonthly Avg MinPrevious Permit LimitSampling FrequencyReporting FrequencySan Ty		mg/L	2, 3	4.3		1.4	*/*	1/quarter	quarterly	G
PARAMETERUnitBasis for LimitsMinimumMaximumPrevious Permit LimitSampling FrequencyReporting FrequencySam TypHSU16.59.0 ≥ 6.0 1/quarterquarterlyOPARAMETERUnitBasis for LimitsImage: Sampling for LimitsMonthly Avg MinPrevious Permit LimitSampling FrequencyReporting Reporting FrequencySampling Frequency	· · · · · · · · · · · · · · · · · · ·	mg/L	2, 3	9.3		2.8	*/*	1/quarter	quarterly	G
PARAMETERUnitfor LimitsMinimumMaximumPermit LimitSampling FrequencyReporting FrequencySampling TypHSU16.59.0 ≥ 6.0 1/quarterquarterlyOPARAMETERUnitBasis for LimitsCMonthly Avg MinPrevious Permit LimitSampling FrequencyReporting FrequencySampling Ty	Oil & Grease	mg/L	8	*		*	***	1/quarter	quarterly	G
PARAMETER Unit Basis for Limits Monthly Avg Min Previous Permit Limit Sampling Frequency Reporting Frequency Sam	PARAMETER	Unit	for	Minimum		Maximum	Permit			Sample Type
PARAMETER Unit for Limits I for Limits Avg Min Permit Limit Sampling Reporting Sampling Frequency Ty	pH	SU	1	6.5		9.0	≥ 6.0	1/quarter	quarterly	G
BOD ₅ Percent Removal % 1 65 65 1/quarter quarterly N	PARAMETER	Unit	for			2	Permit			Sample Type
	BOD ₅ Percent Removal	%	1			65	65	1/quarter	quarterly	М
TSS Percent Removal % 1 65 65 1/quarter quarterly M	TSS Percent Removal	%	1			65	65	1/quarter	quarterly	М

* - Monitoring requirement only.

** - #/100mL; the Monthly Average for E. coli is a geometric mean.

*** - Parameter not previously established in previous state operating permit.

Basis for Limitations Codes:

- State or Federal Regulation/Law 1. 2.
 - Water Quality Standard (includes RPA)
- 3. Water Quality Based Effluent Limits
 - 7. 8.

**** - C = 24-hour composite G = Grab

T = 24-hr. total

E = 24-hr. estimate

M = Measured/calculated

9. WET Test Policy

Multiple Discharger Variance 10.

4. Antidegradation Review

- Antidegradation Policy 5.
- Water Quality Model 6.
- Best Professional Judgment
- TMDL or Permit in lieu of TMDL

OUTFALL #001 - DERIVATION AND DISCUSSION OF LIMITS:

- **Flow**. In accordance with [40 CFR Part 122.44(i)(1)(ii)] the volume of effluent discharged from each outfall is needed to assure compliance with permitted effluent limitations. If the permittee is unable to obtain effluent flow, then it is the responsibility of the permittee to inform the Department, which may require the submittal of an operating permit modification.
- <u>Biochemical Oxygen Demand (BOD₅)</u>. Effluent limitations have been retained from previous state operating permit, please see the APPLICABLE DESIGNATION OF WATERS OF THE STATE sub-section of the <u>Effluent Limits Determination</u>.
- <u>Total Suspended Solids (TSS)</u>. Effluent limitations have been retained from previous state operating permit, please see the **APPLICABLE DESIGNATION OF WATERS OF THE STATE** sub-section of the <u>Effluent Limits Determination</u>.

Please note that the final effluent limits for BOD and TSS contained in the permit are Equivalent to Secondary limits as per 10 CSR 20-7.015. Any changes made to the lagoon system that modifies it such that it no longer functions as a typical lagoon will result in the facility no longer qualifying for Equivalent to Secondary limitations. The facility may be required to also to follow the Missouri Antidegradation Rule and Implementation Procedure if the discharge is expanded.

- <u>Escherichia coli (E. coli)</u>. Monthly average of 206 per 100 mL as a geometric mean and Weekly Average of 1,030 per 100 mL as a geometric mean during the recreational season (April 1 October 31), to protect Whole Body Contact Recreation (B) designated use of the receiving stream, as per 10 CSR 20-7.031(5)(C). An effluent limit for both monthly average and weekly average is required by 40 CFR 122.45(d). The Geometric Mean is calculated by multiplying all of the data points and then taking the nth root of this product, where n = # of samples collected. For example: Five *E. coli* samples were collected with results of 1, 4, 6, 10, and 5 (#/100mL). Geometric Mean = 5th root of (1)(4)(6)(10)(5) = 5th root of 1,200 = 4.1 #/100mL.
- <u>Total Ammonia Nitrogen</u>. Early Life Stages Present Total Ammonia Nitrogen criteria apply [10 CSR 20-7.031(5)(B)7.C. & Table B3]. Background total ammonia nitrogen = 0.01 mg/L. No mixing considerations allowed; therefore, WLA = appropriate criterion.

Season	Temp (°C)	pH (SU)	Total Ammonia Nitrogen CCC (mg/L)	Total Ammonia Nitrogen CMC (mg/L)
Summer	26	7.8	1.5	12.1
Winter	6	7.8	3.1	12.1

Summer: April 1 – September 30 $C_e = ((0.02 + 0.0)1.5 - (0.0 * 0.01))/0.02$ Chronic WLA: $C_{e} = 1.5 \text{ mg/L}$ $C_e = ((0.02 + 0.0)12.1 - (0.0 * 0.01))/0.02$ Acute WLA: $C_e = 12.1 \text{ mg/L}$ $[CV = 0.78, 99^{th} Percentile, 30 day avg.]$ $LTA_{c} = 1.5 \text{ mg/L} (0.727) = 1.09 \text{ mg/L}$ $[CV = 0.78, 99^{th} Percentile]$ $LTA_a = 12.1 \text{ mg/L} (0.2556) = 3.09 \text{ mg/L}$ Use most protective number of LTA_c or LTA_a. MDL = 1.09 mg/L (3.912) = 4.3 mg/L $[CV = 0.78, 99^{th} Percentile]$ $[CV = 0.78, 95^{th} Percentile, n = 30]$ AML = 1.09 mg/L (1.25) = 1.4 mg/LWinter: October 1 – March 31 Chronic WLA: $C_e = ((0.02 + 0.0)3.1 - (0.0 * 0.01))/0.02$ $C_{e} = 3.1 \text{ mg/L}$ $C_e = ((0.02 + 0.0)12.1 - (0.0 * 0.01))/0.02$ Acute WLA: $C_e = 12.1 \text{ mg/L}$ $[CV = 0.86, 99^{th} Percentile, 30 day avg.]$ $LTA_c = 3.1 \text{ mg/L} (0.704) = 2.18 \text{ mg/L}$ $[CV = 0.86, 99^{th} Percentile]$ $LTA_a = 12.1 \text{ mg/L} (0.234) = 2.83 \text{ mg/L}$ Use most protective number of LTA_c or LTA_a.

MDL = 2.18 mg/L (4.28) = 9.3 mg/L	$[CV = 0.86, 99^{th} Percentile]$
AML = 2.18 mg/L (1.28) = 2.8 mg/L	$[CV = 0.86, 95^{th} Percentile, n = 30]$

- <u>Oil & Grease</u>. Monitoring only requirement to see if the discharge has the reasonable potential to violate Water Quality Standards. This data will be reviewed during the next permit renewal.
- <u>pH</u>. 6.5 9.0 SU. pH limitations of 6.0-9.0 SU [10 CSR 20-7.015] are not protective of the in-stream Water Quality Standard, which states that water contaminants shall not cause pH to be outside the range of 6.5 9.0 SU. Due to the classification of the receiving stream, the Department has determined that there is no assimilative capacity during critical low flow periods; therefore the water quality standard must be met at the outfall.
- <u>Biochemical Oxygen Demand (BOD₅) Percent Removal</u>. In accordance with 40 CFR Part 133.102(a)(3) & (b)(3), removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD₅) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals. This facility is required to meet 65% removal efficiency for BOD₅.
- <u>Total Suspended Solids (TSS) Percent Removal</u>. In accordance with 40 CFR Part 133.105(a)(3) & (b)(3), removal efficiency is a method by which the Federal Regulations define Secondary Treatment and Equivalent to Secondary Treatment, which applies to Biochemical Oxygen Demand 5-day (BOD₅) and Total Suspended Solids (TSS) for Publicly Owned Treatment Works (POTWs)/municipals. This facility is required to meet 65% removal efficiency for TSS.
- **<u>Parameters Removed</u>**. Temperature was removed as the permit writer did not observe a reasonable potential to violate water quality standards.

Sampling Frequency Justification:

Sampling and Reporting Frequency was changed to quarterly due to the small flows from the facility. Sampling for *E. coli* is set at quarterly per 10 CSR 20-7.015(9)(D)6.C.

Sampling Type Justification:

As per 10 CSR 20-7.015, BOD₅ and TSS collected for lagoons may be grab samples. Grab samples must be collected for pH, Ammonia as N, *E. coli*, and Oil & Grease. This is due to the holding time restriction for *E. coli*, the volatility of Ammonia, and the fact that pH cannot be preserved and must be sampled in the field. As Ammonia and Oil & Grease samples must be immediately preserved, these samples are to be collected as a grab. For further information on sampling and testing methods please review 10 CSR 20-7.015(9)(D) 2.

OUTFALL #001 – GENERAL CRITERIA CONSIDERATIONS:

In accordance with 40 CFR 122.44(d)(1), effluent limitations shall be placed into the permit for those pollutants which have been determined to cause, have the reasonable potential to cause, or contribute to an excursion above any State water quality standard, including State narrative criteria for water quality. The rule further states that pollutants which have been determined to cause, have the reasonable potential to cause, or contribute to an excursion above a narrative criterion within an applicable State water quality standard, the permit shall contain a numeric effluent limitation to protect that narrative criterion. In order to comply with this regulation, the permit writer will complete reasonable potential determinations on whether the discharge will violate any of the general criteria listed in 10 CSR 20-7.031(4). These specific requirements are listed below followed by derivation and discussion (the lettering matches that of the rule itself, under 10 CSR 20-7.031(4)). It should also be noted that Section 644.076.1, RSMo as well as Section D – Administrative Requirements of Standard Conditions Part I of this permit states that it shall be unlawful for any person to cause or permit any discharge of water contaminants from any water contaminant or point source located in Missouri that is in violation of sections 644.006 to 644.141 of the Missouri Clean Water Law or any standard, rule or regulation promulgated by the commission.

- (A) Waters shall be free from substances in sufficient amounts to cause the formation of putrescent, unsightly or harmful bottom deposits or prevent full maintenance of beneficial uses. The discharge from this facility is made up of treated domestic wastewater. Based upon review of the most recent Report of Compliance Inspection, dated November 15, 2013, no evidence of an excursion of this criterion has been observed by the Department in the past and the facility has not disclosed any other information related to the characteristics of the discharge on their permit application which has the potential to cause or contribute to an excursion of this narrative criterion. Additionally, this facility utilizes equivalent to secondary treatment technology and is currently in compliance with the equivalent to secondary treatment technology based effluent limits established in this permit and there has been no indication to the Department that the stream has had issues maintaining beneficial uses as a result of this discharge. Based on the information reviewed during the drafting of this permit, these final effluent limitations appear to have protected against the excursion of this criterion in the past. Therefore, the discharge does not have the reasonable potential to cause or contribute to an excursion of this criterion.
- (B) Waters shall be free from oil, scum and floating debris in sufficient amounts to be unsightly or prevent full maintenance of <u>beneficial uses</u>. Please see (A) above as justification is the same.
- (C) Waters shall be free from substances in sufficient amounts to cause unsightly color or turbidity, offensive odor or prevent full maintenance of beneficial uses. Please see (A) above as justification is the same.

- (D) Waters shall be free from substances or conditions in sufficient amounts to result in toxicity to human, animal or aquatic life. This permit contains final effluent limitations which are protective of both acute and chronic toxicity for various pollutants that are either expected to be discharged by domestic wastewater facilities or that were disclosed by this facility on the application for permit coverage. Based on the information reviewed during the drafting of this permit, it has been determined if the facility meets final effluent limitations established in this permit, there is no reasonable potential for the discharge to cause an excursion of this criterion.
- (E) <u>There shall be no significant human health hazard from incidental contact with the water</u>. Please see (D) above as justification is the same.
- (F) There shall be no acute toxicity to livestock or wildlife watering. Please see (D) above as justification is the same.
- (G) <u>Waters shall be free from physical, chemical or hydrologic changes that would impair the natural biological community</u>. Please see (A) above as justification is the same.
- (H) Waters shall be free from used tires, car bodies, appliances, demolition debris, used vehicles or equipment and solid waste as defined in Missouri's Solid Waste Law, section 260.200, RSMo, except as the use of such materials is specifically permitted pursuant to section 260.200-260.247. The discharge from this facility is made up of treated domestic wastewater. No evidence of an excursion of this criterion has been observed by the Department in the past and the facility has not disclosed any other information related to the characteristics of the discharge on their permit application which has the potential to cause or contribute to an excursion of this narrative criterion. Additionally, any solid wastes received or produced at this facility are wholly contained in appropriate storage facilities, are not discharged, and are disposed of offsite. This discharge is subject to Standard Conditions Part III, which contains requirements for the management and disposal of sludge to prevent its discharge. Therefore, this discharge does not have reasonable potential to cause or contribute to an excursion of this criterion.

Part VIII - Cost Analysis for Compliance

Pursuant to Section 644.145, RSMo, when issuing permits under this chapter that incorporate a new requirement for discharges from publicly owned combined or separate sanitary or storm sewer systems or publicly owned treatment works, or when enforcing provisions of this chapter or the Federal Water Pollution Control Act, 33 U.S.C. 1251 et seq., pertaining to any portion of a publicly owned combined or separate sanitary or storm sewer system or [publicly owned] treatment works, the Department of Natural Resources shall make a "finding of affordability" on the costs to be incurred and the impact of any rate changes on ratepayers upon which to base such permits and decisions, to the extent allowable under this chapter and the Federal Water Pollution Control Act. This process is completed through a cost analysis for compliance. Permits that do not include new requirements may be deemed affordable.

 \square - The Department is required to determine "findings of affordability" because the permit applies to a combined or separate sanitary sewer system for a publically-owned treatment works.

Cost Analysis for Compliance - The Department has made a reasonable search for empirical data indicating the permit is affordable. The search consisted of a review of Department records that might contain economic data on the community, a review of information provided by the applicant as part of the application, and public comments received in response to public notices of this draft permit. If the empirical cost data was used by the permit writer, this data may consist of median household income, any other ongoing projects that the Department has knowledge, and other demographic financial information that the community provided as contemplated by Section 644. 145.3. See **Appendix – Cost Analysis for Compliance**

- The Department is not required to determine Cost Analysis for Compliance because the permit contains no new conditions or requirements that convey a new cost to the facility.

Part IX – Administrative Requirements

On the basis of preliminary staff review and the application of applicable standards and regulations, the Department, as administrative agent for the Missouri Clean Water Commission, proposes to issue a permit(s) subject to certain effluent limitations, schedules, and special conditions contained herein and within the operating permit. The proposed determinations are tentative pending public comment.

PERMIT SYNCHRONIZATION:

The Department of Natural Resources is currently undergoing a synchronization process for operating permits. Permits are normally issued on a five-year term, but to achieve synchronization many permits will need to be issued for less than the full five years allowed by regulation. The intent is that all permits within a watershed will move through the Watershed Based Management (WBM) cycle together will all expire in the same fiscal year. This will allow further streamlining by placing multiple permits within a smaller geographic area on public notice simultaneously, thereby reducing repeated administrative efforts. This will also allow the Department to explore a watershed based permitting effort at some point in the future. Renewal applications must continue to be submitted within 180 days of expiration, however, in instances where effluent data from the previous renewal is less than 4 years old, that data may be re-submitted to meet the requirements of the renewal application. If the permit provides a schedule of compliance for meeting new water quality based effluent limits beyond the expiration date of the permit, the time remaining in the schedule of compliance will be allotted in the renewed permit. This permit will expire in the 3rd Quarter of calendar year 2019. If the Department issues the permit at this time, the effective period of the permit would be less than one year in length. To ensure efficient use of Department staff, reduce the Department's permitting back log and to provide better service to the permittee by avoiding another renewal application to be submitted in such a short time period this operating permit will be issued for the maximum timeframe of five years and synced with other permits in the watershed at a later date.

PUBLIC NOTICE:

The Department shall give public notice that a draft permit has been prepared and its issuance is pending. Additionally, public notice will be issued if a public hearing is to be held because of a significant degree of interest in and water quality concerns related to a draft permit. No public notice is required when a request for a permit modification or termination is denied; however, the requester and permittee must be notified of the denial in writing. The Department must issue public notice of a pending operating permit or of a new or reissued statewide general permit. The public comment period is the length of time not less than 30 days following the date of the public notice which interested persons may submit written comments about the proposed permit. For persons wanting to submit comments regarding this proposed operating permit, then please refer to the Public Notice page located at the front of this draft operating permit. The Public Notice page gives direction on how and where to submit appropriate comments.

□ - The Public Notice period for this operating permit was from August 31, 2018 to October 1, 2018. Responses to the Public Notice of this operating permit did not warrant the modification of effluent limits and/or the terms and conditions of this permit. A public comment was submitted by the Boone County Regional Sewer District providing an update of the current annual operating costs contained in the Fact Sheet Appendix - Cost Analysis for Compliance (CAFCOM). The CAFCOM was updated with the information.

DATE OF FACT SHEET: OCTOBER 26, 2018

COMPLETED BY:

BRANT FARRIS, ENVIRONMENTAL SPECIALIST III MISSOURI DEPARTMENT OF NATURAL RESOURCES WATER PROTECTION PROGRAM OPERATING PERMITS SECTION - DOMESTIC WASTEWATER UNIT (660) 385-8019 brant.farris@dnr.mo.gov

Appendices

APPENDIX - CLASSIFICATION WORKSHEET:

ATTENDIX - CLASSIFICATION WORKSHEET;		_
Ітем	POINTS POSSIBLE	POINTS Assigned
Maximum Population Equivalent (P.E.) served (Max 10 pts.)	1 pt./10,000 PE or major fraction thereof.	
Maximum: 10 pt Design Flow (avg. day) or peak month; use greater (Max 10 pts.)	1 pt. / MGD or major fraction thereof.	
EFFLUENT DISCHARGE RECEIVING	WATER SENSITIVITY:	
Missouri or Mississippi River	0	
All other stream discharges except to losing streams and stream reaches supporting whole body contact	1	
Discharge to lake or reservoir outside of designated whole body contact recreational area	2	
Discharge to losing stream, or stream, lake or reservoir area supporting whole body contact recreation	3	3
PRELIMINARY TREATMEN	Γ - Headworks	
Screening and/or comminution	3	
Grit removal	3	
Plant pumping of main flow (lift station at the headworks)	3	
PRIMARY TREATM	ENT	
Primary clarifiers	5	
Combined sedimentation/digestion	5	
Chemical addition (except chlorine, enzymes)	4	
REQUIRED LABORATORY CONTROL – performed	by plant personnel (highest level only)	
Push – button or visual methods for simple test such as pH, Settleable solids	3	
Additional procedures such as DO, COD, BOD, titrations, solids, volatile content	5	5
More advanced determinations such as BOD seeding procedures, fecal coliform, nutrients, total oils, phenols, etc.	7	
Highly sophisticated instrumentation, such as atomic absorption and gas chromatograph	10	
ALTERNATIVE FATE OF I	EFFLUENT	
Direct reuse or recycle of effluent	6	
Land Disposal – low rate	3	
High rate	5	
Overland flow	4	
Total from page ONE (1)		8

APPENDIX - CLASSIFICATION WORKSHEET (CONTINUED):	POINTS
Item	POINTS POSSIBLE	ASSIGNED
VARIATION IN RAW WASTE (highest level only) (DMR e	exceedances and Design Flow excee	dances)
Variation do not exceed those normally or typically expected	0	0
Recurring deviations or excessive variations of 100 to 200 % in strength and/or flow	2	
Recurring deviations or excessive variations of more than 200 % in strength and/or flow	4	
Raw wastes subject to toxic waste discharge	6	
SECONDARY TREATM	MENT	
Trickling filter and other fixed film media with secondary clarifiers	10	
Activated sludge with secondary clarifiers (including extended aeration and oxidation ditches)	15	
Stabilization ponds without aeration	5	
Aerated lagoon	8	8
Advanced Waste Treatment Polishing Pond	2	
Chemical/physical – without secondary	15	
Chemical/physical – following secondary	10	
Biological or chemical/biological	12	
Carbon regeneration	4	
DISINFECTION		
Chlorination or comparable	5	
Dechlorination	2	
On-site generation of disinfectant (except UV light)	5	
UV light	4	4
SOLIDS HANDLING - SI	LUDGE	
Solids Handling Thickening	5	
Anaerobic digestion	10	
Aerobic digestion	6	
Evaporative sludge drying	2	
Mechanical dewatering	8	
Solids reduction (incineration, wet oxidation)	12	
Land application	6	
Total from page TWO (2)		12
Total from page ONE (1)		8
Grand Total		20

ADDENDIX CLASSI CATION WORKS (00)

 \square - A: 71 points and greater \square - B: 51 points – 70 points \square - C: 26 points – 50 points \square - D: 0 points – 25 points

APPENDIX – RPA RESULTS:

Parameter	CMC*	RWC Acute*	CCC*	RWC Chronic*	n**	Range max/min	CV***	MF	RP Yes/No
Total Ammonia as Nitrogen (Summer) mg/L	12.1	71.35	1.5	71.35	27.00	28.8/0.3	0.78	2.48	YES
Total Ammonia as Nitrogen (Winter) mg/L	12.1	85.52	3.1	85.52	30.00	33.6/0.3	0.86	2.55	YES

N/A – Not Applicable

* - Units are (μ g/L) unless otherwise noted.

** - If the number of samples is 10 or greater, then the CV value must be used in the WQBEL for the applicable constituent. If the number of samples is < 10, then the default CV value must be used in the WQBEL for the applicable constituent.

*** - Coefficient of Variation (CV) is calculated by dividing the Standard Deviation of the sample set by the Mean of the same sample set.

RWC – Receiving Water Concentration. It is the concentration of a toxicant or the parameter toxicity in the receiving water after mixing (if applicable).

n - Is the number of samples.

MF – Multiplying Factor. 99% Confidence Level and 99% Probability Basis.

RP – Reasonable Potential. It is where an effluent is projected or calculated to cause an excursion above a water quality standard based on a number of factors including, as a minimum, the four factors listed in 40 CFR 122.44(d)(1)(ii).

Reasonable Potential Analysis is conducted as per (TSD, EPA/505/2-90-001, Section 3.3.2). A more detailed version including calculations of this RPA is available upon request.

APPENDIX – COST ANALYSIS FOR COMPLIANCE:

Missouri Department of Natural Resources Water Protection Program Cost Analysis for Compliance (In accordance with RSMo 644.145)

Hartsburg WWTF, Permit Renewal Village of Hartsburg Missouri State Operating Permit #MO-0108995

Section 644.145 RSMo requires the Department of Natural Resources ("Department" or "DNR") to make a "finding of affordability" when "issuing permits under" or "enforcing provisions of" state or federal clean water laws "pertaining to any portion of a combined or separate sanitary sewer system for publicly-owned treatment works." This cost analysis does not dictate that a permittee will upgrade their facility, or how the permittee will comply with the new permit requirements.

This cost analysis is based on data available to the Department as provided by the permittee and data obtained from readily available sources. For the most accurate analysis, it is essential that the permittee provides the Department with current information about the City's financial and socioeconomic situation. The financial questionnaire available to permittees on the DNR website (http://dnr.mo.gov/forms/780-2511-f.pdf) should have been submitted with the permit renewal application. If it was not submitted with the renewal application, the Department sent a request to complete the form with the welcome letter. The Department currently estimates the cost for reconstruction of a treatment plant using a software program from Hydromantis¹ titled CAPDETWORKS (CapDet). CapDet is a preliminary design and costing software program for wastewater treatment plants utilizing national indices, such as the Marshall and Swift Index and Engineering News Records Cost Index to price the development of capital, operating, maintenance, material, and energy costs for each treatment technology. The program works from national indices therefore; the estimated costs are expected to be higher than actual costs as each community is unique in its budget commitments and treatment design. The cost estimates located within this document are for the construction of a brand new treatment facility or system that is the most practical to facilitate compliance with new requirements.

The Department is required to issue a permit with final effluent limits in accordance with 644.051.1.(1) RSMo, 644.051.1.(2) RSMo, and the Clean Water Act. The table below summarizes the results of this cost analysis. The practical result of this analysis is to incorporate an adequate compliance schedule into the permit that will mitigate the financial burden of the new permit requirements.

	Cost mary sis for	Compliance Summar	y rabic	
Estimated present worth to upgrade to a land application system	Median Household Income (MHI) for the Village of Hartsburg	Estimated monthly cost per user as a percent of MHI	Financial Burden	Schedule of Compliance to meet Ammonia
\$404,596 - \$683,215	\$39,871	1.1% - 1.6%	Medium	10 years

Cost Analysis for Compliance Summary Table

Flow evaluated: 14,400 gpd

Residential Connections:	49
Commercial Connections:	6
Industrial Connections:	0
Total Connections for this facility:	55

New Permit Requirements:

The permit requires compliance with new effluent limitations for ammonia, which may require the design, construction and operation of different treatment technology. The cost assumptions in this cost analysis anticipate complete replacement of the existing treatment facility. To calculate the estimated user cost per 5,000 gallons, the Department used the equations currently being used in the Financial Assistance Center's rate calculator. The equations account for replacement of equipment during the life of the treatment facility, debt retirement, capital costs, and an inflation factor. The calculator evaluates multiple technologies through CapDet at a range of flows, then, using a linear interpolation, develops a spreadsheet outlining high and low costs for treatment plants. For this analysis the Department has selected the mechanical treatment technology that could be the most practical solution to meet the new requirements for the community as well as cost estimation to install a land application system. Because the methods used to derive the analysis estimate costs that are greater than actual costs associated with an upgrade, it reflects a conservative estimate anticipated for a community. An overestimation of costs is due to the fact that it is not possible for the permit writer to determine what existing equipment and structures will be reused in the upgraded facility before an engineer completes a facility design.

The permit also requires compliance with new monitoring requirements for Oil & Grease.

The size of the facility evaluated for upgrades was chosen based on the permitted design flow. If significant population growth is expected in the community, or if a significant portion of the flow is due to I&I, the flows used in the Facility Plan prepared by a consulting engineer may be different than this flow and the estimated costs within this analysis.

Anticipated Costs Associated with Complying with the New Requirements:

Costs associated with land application:

The total present worth estimated to purchase land and install a land application system is between \$404,596 and \$683,215 (*CAPDETWORKS cost estimator was used*). The user costs over a thirty year period are estimated to be between \$35.15 and \$55.67 per household per month. The low cost estimate for land application assumes that the community will not have to construct or purchase additional land for a new storage basin. The high cost estimate assumes the purchase of additional land and the construction of a new storage basin. The estimation includes the purchase of a minimum of 12.3 acres and a maximum of 13.5 acres. Four regions divided by highways have been established to estimate the minimum storage time required and the amount of land necessary for land application within the State. The cost of land has been estimated based on county averages. The regions are north of Highway 36, between Highways 36 and 50, between Highways 50 and 60, and south of Highway 60. For communities that are divided by highways, the region selected is where the majority of the county resides. The acreage estimated through CapDet does not reflect sitespecific conditions and more or less land may be required based on site-specific considerations, such as streams, sinkholes, severe slopes, or roads. A no discharge facility, of which land application is the most common form, is required to be demonstrated as infeasible before a discharging system may be constructed per [10 CSR 20-6.010(4)(D).] When land is available, it is the Department's stance that land application is an important treatment option to be considered because of the expected lower cost associated with construction and operation and maintenance over a longer term. Also, the no discharge system is of value to the permittee when considering additional costs associated with possible future changes to Water Quality Standards.

Cost associated with mechanical treatment:

The costs estimated in CAPDETWORKS are associated with a complete reconstruction of a new treatment plant. The total present worth for complete replacement of the existing treatment facility in order to meet new ammonia effluent limits is estimated at 1,093,091 (*CAPDETWORKS cost estimator was used*). This cost, if financed through user fees, might cost each household approximately \$99.34 per month. The Department has estimated the construction and treatment costs for an extended aeration package plant. The treatment type has been set to meet effluent ammonia limits of 0.6 mg/L and losing stream criteria for BOD₅ and TSS. Sludge handling and sludge treatment was not included in the capital, operations, maintenance, and present worth cost estimations. Disinfection is not represented in the present worth listed in this paragraph, as it was discussed in the previous paragraph. It is the Department's opinion that an extended aeration package plant is the most practical mechanical treatment technology for your community based on the current design flow. A more detailed engineering and design report conducted for your specific facility will be completed by your hired engineer. This may reflect a different type of treatment option than what is described within this analysis and may include additional sludge removal and handling costs, collection system work, or additional upgrades at the treatment plant. These costs will be used to complete this analysis.

Cost associated with new sampling requirements:

The total cost estimated for new quarterly monitoring requirements is \$280 annually. This cost, if financed through user fees, might cost each household an extra \$0.43 per month. A community sets their user rates based on several factors. The percentage of the current user rate that is available to cover new debt is unknown to the Department.

For any questions associated with the CAPDETWORKS cost estimator, please contact the Engineering Section at (573) 751-6621.

(1) A community's financial capability and ability to raise or secure necessary funding;

Current Monthly User Rates per 5,000 gallons:	\$30		
Municipal Bond Rating (if applicable):	Not found nor provided		
Bonding Capacity: (General Obligation Bond capacity allowed by constitution: cities=up to 20% of taxable tangible property sewer districts or villages=up to 5% of taxable tangible property)	\$220,038		
Median household income (MHI): ²	\$39,871		
Current outstanding debt for the WWTP:	\$0		
Amount within the current user rate used toward payments on outstanding debt related to the current wastewater infrastructure:	\$0		

(2) Affordability of pollution control options for the individuals or households at or below the median household income level of the community;

A Current Costs

	Current annual operating costs (exclude depreciation):	~\$9,677
B-1	Estimated Costs for Mechanical Plant Pollution Control Option	
	Estimated total present worth of pollution control:*	\$1,093,091
	Estimated capital cost of pollution control:**	\$351,440
	Annual cost of operation and maintenance:***	\$59,512
	Estimated resulting user cost per household per month:****	\$99.34
	Estimated resulting user cost per household per month plus the cost for new sampling:	\$99.77
	Cost per household as a percent of median household income: ³	3.0%
	Estimated cost per household per month plus the cost for new sampling:	3.0%

These costs assume a 5% interest rate over 20 years for mechanical treatment. All treatment technologies were set to meet effluent ammonia limits of less than 0.6 mg/L and losing stream criteria for BOD₅ and TSS. Sludge handling, sludge treatment, and disinfection were not included in the capital, operations and maintenance, and present worth cost estimations.

B-2 Estimated Costs for Land Application Pollution Control Options

Estimated total present worth of pollution control:*	\$404,596 - \$683,215
Estimated capital cost of pollution control:**	\$327,935 - \$421,585
Land required:	12.3 acres to 13.5 acres
Annual cost of operation and maintenance:***	\$8,337 - \$20,695
Estimated resulting user cost per household per month:****	\$35.18 - \$55.67
Estimated resulting user cost per household per month plus the cost for new sampling:	\$35.61 - \$56.10
Cost per household as a percent of median household income: ⁵	1.1% - 1.7%
Estimated cost per household per month plus the cost for new sampling: ⁶	1.1% - 1.7%

All estimated costs for land application assume a 5% interest rate over 30 years. The estimated capital cost assumes the City must purchase the land. If the City already owns the land, the resulting costs will be less than what is described in Table B-2.

* Total Present Worth includes a five percent interest rate to construct and perform annual operation and maintenance of the new treatment plant over the term of the loan.

** Capital Cost includes project costs from CapDet with design, inspection and contingency costs.

*** O&M cost shown in Tables B-1 and B-2 includes operations, maintenance, materials, chemical and electrical costs for the facility on an annual basis. It includes items that are expected to replace during operations, such as pumps. O&M is estimated between 15% and 45% of the user cost.

**** The Estimated User Cost shown in Tables B-1 and B-2 is composed of two factors, Operation & Maintenance (O&M), and Debt Retirement Costs.

(3) An evaluation of the overall costs and environmental benefits of the control technologies;

The investment in wastewater treatment will provide several social, environmental and economic benefits. Improved wastewater provides benefits such as avoided health costs due to water-related illness, enhanced environmental ecosystem quality, and improved natural resources. The preservation of natural resources has been proven to increase the economic value and sustainability of the surrounding communities. Maintaining Missouri's water quality standards fulfill the goals of restoring and maintaining the chemical, physical and biological integrity of the receiving stream; and, where attainable, to achieves a level of water quality that provides for the protection and propagation of fish, shellfish, wildlife and recreation in and on the water.

Total Ammonia Nitrogen Treatment

Ammonia can be toxic to aquatic life. Fish may suffer a loss of equilibrium, hyperexcitability, increased respiratory activity and oxygen uptake, and increased heart rate. At extreme ammonia levels, fish may experience convulsions, coma, and death. Therefore, final water quality based effluent limits for total ammonia nitrogen are requirement of this Missouri State Operating Permits. A schedule of compliance is given with the final limits so that the permittee has time to secure funding and update their treatment plant, if necessary. Please see the Water Protection Program fact sheet titled "Changes to the Water Quality Standard for Ammonia" at http://dnr.mo.gov/pubs/pub2481.htm.

Native fish and other native aquatic life are extremely important to Missouri's ecosystem. They contribute essential nutrients to the streams, rivers, lakes, pond other waters in which they inhabit. Freshwater ecosystems are important for human survival, in that it provides a majority of people's drinking water. Also, a pristine freshwater ecosystem with an abundance of aquatic life can increase the community's overall income of revenue. Revenue to businesses and sales tax revenue is increased as the natural amenity will attract fisherman and tourism to the area. Fish and other aquatic life also provide a source of low cost sustenance for the people within the surrounding communities.

The construction and installation of land application is another option that has been evaluated within this document. The Missouri State Operating Permit for a land application system does not contain discharge effluent limits as there is no potential to cause an excursion of water quality standards. Therefore, a land application system is of value to the permittee when considering costs associated with operation and maintenance, and future regulatory changes.

(4) Inclusion of ongoing costs of operating and maintaining the existing wastewater collection and treatment system, including payments on outstanding debts for wastewater collection and treatment systems when calculating projected rates:

The community has reported that they have no outstanding debts for the current wastewater collection and treatment systems.

- (5) An inclusion of ways to reduce economic impacts on distressed populations in the community, including but not limited to low and fixed income populations. This requirement includes but is not limited to:
 - (a) Allowing adequate time in implementation schedules to mitigate potential adverse impacts on distressed populations resulting from the costs of the improvements and taking into consideration local community economic considerations.

A schedule of compliance will be provided based on the results of this cost analysis. The schedule of compliance is provided to ensure that the entity has time to reasonably plan for compliance with the new permit requirements. The time provided ensures the entity has time to hire an engineer, develop facility plans, hold community meetings, seek an appropriate funding source, and construct the facility. This analysis has determined the community may endure a medium financial burden. Therefore, a longer schedule of compliance has been provided to allow for the permit holder to adequately plan toward compliance. For compliance assistance, please visit the Department's Community Assistance webpage at https://dnr.mo.gov/assistance/. If it is determined by the permittee that a longer schedule of compliance is necessary due to financial reasons, please contact the permit writer and request modification of the permit schedule.

An integrated plan may be an appropriate option if they community needs to meet other environmental obligations as well as the new requirements within this permit. The integrated plan needs to be well thought out with specific timeframes built into the management plan in which the municipality can reasonably commit. The plan should be designed to allow your municipality to meet their Clean Water Act obligations by maximizing their infrastructure improvement dollars through the appropriate sequencing of work. For further information on how to develop an integrated plan, please see the Department publication, "Missouri Integrated Planning Framework," at http://dnr.mo.gov/pubs/pub2684.htm.

If the permittee can demonstrate that the proposed pollution controls result in substantial and widespread economic and social impact, the permittee may use Factor 6 of the Use Attainability Analysis (UAA) 40 CFR 131.10(g)(6) in the form of a variance. This process is completed by determining the treatment type with the highest attainable effluent quality that would not result in a socio-economic hardship. For more information on variance requests, please contact the Water Protection Program's Special Projects Coordinator at 573-751-9391.

- (b) Allowing for reasonable accommodations for regulated entities when inflexible standards and fines would impose a disproportionate financial hardship in light of the environmental benefits to be gained.
- If available, connection to a larger centralized sewer system in the area may be more cost effective for the community. This can be incorporated into an integrated plan.
- An opportunity may exist for the relocation of the point of discharge to a receiving stream capable of a greater mixing zone.
- The permittee may apply for State Revolving Fund (SRF) financial support in order to help fund a Capital Improvements Plan. Other loans and grants also exist for which the facility may be eligible. Contact information for the Department's Financial Assistance Center (FAC) and more information can be found on the Department's website at http://dnr.mo.gov/env/wpp/srf/wastewater-assistance.htm.

Socioeconomic Data: ^{7-11.} The following table characterizes the current overall socioeconomic condition of the community as compared to the overall socioeconomic condition of the State of Missouri. The following information was compiled using the latest U.S. Census data.

No.	Administrative Unit	Hartsburg Town	Missouri State
1	Population (2016)	97	6,059,651
2	Percent Change in Population (2000-2016)	-10.2%	8.3%
3	2016 Median Household Income (in 2017 Dollars)	\$39,871	\$50,417
4	Percent Change in Median Household Income (2000-2016)	-13.2%	-5.9%
5	Median Age (2016)	49.9	38.3
6	Change in Median Age in Years (2000-2016)	4.6	2.2
7	Unemployment Rate (2016)	0.0%	6.6%
8	Percent of Population Below Poverty Level (2016)	12.6%	15.3%
9	Percent of Household Received Food Stamps (2016)	12.3%	13.0%
10	(Primary) County Where the Community Is Located	Boone County	

(6) An assessment of other community investments and operating costs relating to environmental improvements and public health protection;

The Village reported that there is a sewer extension project to extend sewer 600 feet to allow connection to the sewer system from homes annexed within the last seven years. The expense is estimated at \$65,000.

(7) An assessment of factors set forth in the United States Environmental Protection Agency's guidance, including but not limited to the "Combined Sewer Overflow Guidance for Financial Capability Assessment and Schedule Development" that may ease the cost burdens of implementing wet weather control plans, including but not limited to small system considerations, the attainability of water quality standards, and the development of wet weather standards;

<u>Secondary indicators for consideration</u>: The following table below characterizes the community's overall financial capability to raise the necessary funds to meet the new permit requirements.

Indicators	Strong (3 points)	Mid-Range (2 points)	Weak (1 point)	Score
Bond Rating Indicator	Above BBB or Baa	BBB or Baa	Below BBB or Baa	NA
Overall Net Debt as a % of Full Market Property Value	Below 2%	2% - 5%	Above 5%	3
Unemployment Rate (2016)	Beyond 1% below Missouri average of 6.6%	± 1% of Missouri average of 6.6%	Beyond 1% above Missouri average of 6.6%	3
2016 Median Household Income (in 2017 Dollar)	Beyond 25% above Missouri MHI (\$50,417)	± 25% of Missouri MHI (\$50,417)	Beyond 25% below Missouri MHI (\$50,417)	2
Percent of Population Below Poverty Level (2016)	Beyond 10% below Missouri average of 15.3%	± 10% of Missouri average of 15.3%	Beyond 10% above Missouri average of 15.3%	2

Percent of Household Received Food Stamps (2016)	Beyond 5% below Missouri average of 13.0%	± 5% of Missouri average of 13.0%	Beyond 5% above Missouri average of 13.0%	2
Property Tax Revenues as a % of Full Market Property Value	Below 2%	2% - 4%	Above 4%	3
Property Tax Collection Rate	Above 98%	94% - 98%	Below 94%	3
Total Average Score				2.6

Financial Capability Matrix: The results of the Financial Capability Indicator score and the residential indicator calculated above are considered jointly in the Financial Capability Matrix to determine the financial burden that could occur as a result from compliance with the new requirements of the permit.

In the following matrix, the results are a low, medium, or high financial burden. The matrix is used to determine the burden for both of the land application options and the mechanical plant option.

• Financial Capability (FCI) Indicators Average Score:

2.6 3.0% 1.1% - 1.7%

Mechanical Plant Residential Indicator (RI, from Criteria #2 above):
Land Application Residential Indicator (RI, from Criteria #2 above):

Financial Capability	Residential Indicator (User cost as a % of MHI)			
Indicators Score from	Low	Mid-Range	High	
above ↓	(Below 1%)	(Between 1.0% and 2.0%)	(Above 2.0%)	
Weak (below 1.5)	Medium Burden	High Burden	High Burden	
Mid-Range (1.5 – 2.5)	Low Burden	Medium Burden	High Burden	
Strong (above 2.5)	Low Burden	Medium Burden	High Burden	

- Estimated Financial Burden for Mechanical Plant: High Burden
- Estimated Financial Burden for Land Application: Medium Burden

(8) An assessment of any other relevant local community economic condition.

The Village reported that they have limited funds available to afford major changes to the sewer system. The Village is seeking preliminary engineering feedback from Engineering Survey & Services to assist with reviewing the draft permit and analyzing their options.

The Department contracted with Wichita State University to complete an assessment tool that would allow for predictions on rural Missouri community populations and future sustainability. The purpose of the study is to use a statistical modeling analysis in order to determine factors associated with each rural Missouri community that would predict the future population changes that could occur in each community. A stepwise regression model was applied to 19 factors which were determined as predictors of rural population change in Missouri. The model established a hierarchy of the predicting factors which allowed the model to place a weighted value on each of the factors. A total of 745 rural towns and villages in Missouri received a weighted value for each of the predicting factors. The weighted values for each town / village were then added together to determine an overall decision score. The overall decision scores were then divided into five categories and each town was assigned to a different categorical group based on the overall decision score.

The categorical groups were developed from the range of overall scores across all rural towns and villages within Missouri. The range covers 1,191 score points (-245 to 946).

Based on the assessment tool, the Village of Hartsburg has been determined as a category (2) community. This means that the Village of Hartsburg could potentially face more challenging socioeconomic circumstances over time and may have significant declines in population in the future. The Department has determined an adequate schedule of compliance that will alleviate the potential financial burdens the Village of Hartsburg may face due to the necessary upgrades required to meet the new permit requirements. If your community experiences a decline in population which results in the inability to secure the necessary funding for an upgrade to meet the new requirements within this permit, a modification to the schedule of compliance may be necessary. At that time, please contact the Department and send an application for a modification to the schedule of compliance with justification for the time necessary to comply with this permit.

Conclusion and Finding

As a result of new regulations, the Department is proposing modifications to the current operating permit that may require the permittee to upgrade the facility and construct new control technologies and to increase sampling.

The Department considered the eight (8) criteria presented in subsection 644.145 RSMo. when evaluating the cost associated with the relevant actions. Using this analysis, the Department finds that a <u>land application system is the most practical and affordable option</u> for your community. The construction and operation of a land application system will ensure that the individuals within the community will not be required to make unreasonable sacrifices in their essential lifestyle or spending patterns or undergo hardships in order to make the projected monthly payments for sewer connections. Also, a land application treatment system has the potential to generate agricultural revenues that could offset cost. This can include but is not limited to revenue from the sale of a forage or grain crop as well as rent from livestock grazing.

In accordance with 40 CFR § 122.47(a)(1) and 10 CSR 20-7.031(11), compliance must occur as soon as possible. Therefore, based on this analysis including the Rural Population Sustainability Assessment Tool the permit holder has received an ten (10) year schedule of compliance for the design and construction of a land application system with the assumption that land is attainable for the purpose of land application of effluent. The following suggested milestones are an example of a timeline that will keep the permit holder on track to maintain compliance with this permit. It should be noted that once the permit holder's engineer has completed facility design with actual costs associated with compliance of this permit, it may be necessary for the permit holder to request additional time within the schedule of compliance. The Department is committed to review all requests for additional time in the schedule of compliance where adequate justification is provided.

Suggested milestones to meet within each year listed below:

- Year 1. Hire an engineer
- Year 2. Evaluation of rate structure and treatment system and submit an application for renewal of the existing operating permit with new financial and socio-economic data
- Year 3. Evaluation of treatment system
- Year 4. Evaluation of treatment system
- Year 5. Hold bond election
- Year 6. Apply for State Revolving Fund loans and/or grants, and submit facility plan
- Year 7. Apply for Construction Permit and close on loan
- Year 8. Construction
- Year 9. Construction
- Year 10. Complete construction

The schedule of compliance allows the community the first seven years to hire an engineer, evaluate operations and rate structure, obtain an engineering report, hold a bond election, and close on a loan. The remaining three (3) years of the schedule give the community ample time to construct the facility and complete the project. If the community wishes to seek funding from the Department, please contact the Financial Assistance Center for more information. <u>http://www.dnr.mo.gov/env/Wpp/srf/index.html</u>

The Department is committed to reassessing the cost analysis for compliance at renewal to determine if the initial schedule of compliance will accommodate the socioeconomic data and financial capability of the community at that time. In this longer time frame, the Department will work with you to explore the wastewater treatment options that make the most sense for your community. By working more closely with your community, the Department and permittees will be able to identify opportunities to extend the schedule of compliance, if appropriate. Because each community is unique, we want to make sure that you have the opportunity to consider all your options and tailor solutions to best meet your community's needs. The Department understands the economic challenges associated with achieving compliance, and is committed to using all available tools to make an accurate and practical finding of affordability for the communities in the State.

This determination is based on readily available data and may overestimate the financial impact on the community. The community's facility plan that is submitted as a part of the construction permit process includes a discussion of community details, what the community can afford, existing obligations, future growth potential, an evaluation of options available to the community with cost information, and a discussion on no-discharge alternatives. The cost information provided through the facility plan process, which is developed by the community and their engineer, is more comprehensive of the community's individual factors in relation to selected treatment technology and costing information.

References:

- 1. <u>http://www.hydromantis.com/</u>
- (A) 2016 MHI in 2016 Dollar: United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, Table B19013: Median Household Income in the Past 12 Months (in 2016 Inflation-Adjusted Dollars). http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_16_5YR_B19013&prodType=table. (B) 2000 MHI in 1999 Dollar: U.S. Census Bureau (2002) 2000 Census of Population and Housing, Summary Population and Housing Characteristics, PHC-1-27, Missouri, Table 2. Age and Sex: 2000, Washington, DC. http://www.census.gov/prod/cen2000/phc-2-27-pt1.pdf.

(C) 2017 CPI, 2016 CPI and 1999 CPI: For United States, United States Bureau of Labor Statistics (2017) Consumer Price Index - All Urban Consumers, United States City Average. All Items. 1982-84=100.

http://data.bls.gov/timeseries/CUUR0000SA0?data_tool=Xgtable. For Missouri State: United States Bureau of Labor Statistics (2017) Consumer Price Index - All Urban Consumers, Midwest Urban Areas, All Items. 1982-84=100. http://data.bls.gov/timeseries/CUUR0200SA0?data_tool=Xgtable.

(D) 2016 MHI in 2017 Dollar: 2016 MHI in 2016 Dollar x 2017 CPI /2016 CPI; 2000 MHI in 2017 Dollar: 2000 MHI in 1999 Dollar x 2017 CPI /1999 CPI.

(E) Percent Change in Median Household Income (2000-2016) = (2016 MHI in 2017 Dollar - 2000 MHI in 2017 Dollar) / (2000 MHI in 2017 Dollar).

- 3. (\$99.34/(\$39,871/12))100% = 3.0% (mechanical)
- 4. (\$99.77/(\$39,871/12))100% = 3.0% (mechanical + new sampling)
- 5. (\$35.18/(\$39,871/12))100% = 1.1% and (\$55.67/(\$39,871/12))100% = 1.7% (land application)
- 6. (\$35.61/(\$39,871/12))100% = 1.1% and (\$56.10/(\$39,871/12))100% = 1.7% (land application)
- 7. (A) Total Population in 2016: United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, Table B01003: Total Population Universe: Total Population. http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_16_5YR_B01003&prodType=table. (B) Total Population in 2000: U.S. Census Bureau (2002) 2000 Census of Population and Housing, Summary Population and Housing Characteristics, PHC-1-27, Missouri, Table 2. Age and Sex: 2000, Washington, DC. http://www.census.gov/prod/cen2000/phc-2-27-pt1.pdf. (C) Percent Change in Population (2000-2016) = (Total Population in 2016 - Total Population in 2000) / (Total Population in 2000).
- (A) Median Age in 2016: United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, Table B01002: Median Age by Sex Universe: Total population.

http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_16_5YR_B01002&prodType=table. (B) Median Age in 2000: For United States, United States Census Bureau (2002) 2000 Census of Population and Housing, Summary Social, Economic, and Housing Characteristics, PHC-1-1 Part 1. United States Summary, Table 1. Age and Sex: 2000, Washington, DC., Page 2. <u>https://www.census.gov/prod/cen2000/phc-1-1-pt1.pdf</u>. For Missouri State, United States Census Bureau (2002) 2000 Census of Population and Housing, Summary Population and Housing Characteristics, PHC-1-27, Missouri, Table 2. Age and Sex: 2000, Washington, DC., Pages 64-92. <u>http://www.census.gov/prod/cen2000/phc-2-27-pt1.pdf</u>.

- (C) Change in Median Age in Years (2000-2016) = (Median Age in 2016 Median Age in 2000).
- United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, B23025: Employment Status for the Population 16 Years and Over - Universe: Population 16 years and Over. http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS 16 5YR B23025&prodType=table.
- United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, Table S1701: Poverty Status in the Past 12 Months.

http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_16_5YR_S1701&prodType=table.

 United States Census Bureau. 2012-2016 American Community Survey 5-Year Estimates, Table B22003: Receipt of Food Stamps/SNAP in the Past 12 Months by Poverty Status in the Past 12 Months for Households - Universe: Households. <u>http://factfinder.census.gov/faces/tableservices/jsf/pages/productview.xhtml?pid=ACS_16_5YR_B22003&prodType=table</u>.



These Standard Conditions incorporate permit conditions as required by 40 CFR 122.41 or other applicable state statutes or regulations. These minimum conditions apply unless superseded by requirements specified in the permit.

Part I – General Conditions

Section A - Sampling, Monitoring, and Recording

1. Sampling Requirements.

- a. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity.
- b. All samples shall be taken at the outfall(s) or Missouri Department of Natural Resources (Department) approved sampling location(s), and unless specified, before the effluent joins or is diluted by any other body of water or substance.

2. Monitoring Requirements.

a.

- Records of monitoring information shall include:
- i. The date, exact place, and time of sampling or measurements;
- ii. The individual(s) who performed the sampling or measurements;
- iii. The date(s) analyses were performed;
- iv. The individual(s) who performed the analyses;
- v. The analytical techniques or methods used; and
- vi. The results of such analyses.
- b. If the permittee monitors any pollutant more frequently than required by the permit at the location specified in the permit using test procedures approved under 40 CFR Part 136, or another method required for an industry-specific waste stream under 40 CFR subchapters N or O, the results of such monitoring shall be included in the calculation and reported to the Department with the discharge monitoring report data (DMR) submitted to the Department pursuant to Section B, paragraph 7.
- 3. **Sample and Monitoring Calculations.** Calculations for all sample and monitoring results which require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in the permit.
- Test Procedures. The analytical and sampling methods used shall conform 4. to the reference methods listed in 10 CSR 20-7.015 unless alternates are approved by the Department. The facility shall use sufficiently sensitive analytical methods for detecting, identifying, and measuring the concentrations of pollutants. The facility shall ensure that the selected methods are able to quantify the presence of pollutants in a given discharge at concentrations that are low enough to determine compliance with Water Quality Standards in 10 CSR 20-7.031 or effluent limitations unless provisions in the permit allow for other alternatives. A method is "sufficiently sensitive" when; 1) the method minimum level is at or below the level of the applicable water quality criterion for the pollutant or, 2) the method minimum level is above the applicable water quality criterion, but the amount of pollutant in a facility's discharge is high enough that the method detects and quantifies the level of pollutant in the discharge, or 3) the method has the lowest minimum level of the analytical methods approved under 10 CSR 20-7.015. These methods are also required for parameters that are listed as monitoring only, as the data collected may be used to determine if limitations need to be established. A permittee is responsible for working with their contractors to ensure that the analysis performed is sufficiently sensitive.
- 5. Record Retention. Except for records of monitoring information required by the permit related to the permittee's sewage sludge use and disposal activities, which shall be retained for a period of at least five (5) years (or longer as required by 40 CFR part 503), the permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the application for the permit, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Department at any time.

6. Illegal Activities.

- a. The Federal Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the permit shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than two (2) years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than \$20,000 per day of violation, or by imprisonment of not more than (4) years, or both.
- b. The Missouri Clean Water Law provides that any person or who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than \$10,000, or by imprisonment for not more than six (6) months, or by both. Second and successive convictions for violation under this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.

Section B - Reporting Requirements

1. Planned Changes.

- The permittee shall give notice to the Department as soon as possible of any planned physical alterations or additions to the permitted facility when:
 - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b); or
 - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements under 40 CFR 122.42;
 - iii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan;
 - iv. Any facility expansions, production increases, or process modifications which will result in a new or substantially different discharge or sludge characteristics must be reported to the Department 60 days before the facility or process modification begins. Notification may be accomplished by application for a new permit. If the discharge does not violate effluent limitations specified in the permit, the facility is to submit a notice to the Department of the changed discharge at least 30 days before such changes. The Department may require a construction permit and/or permit modification as a result of the proposed changes at the facility.

2. Non-compliance Reporting.

a. The permittee shall report any noncompliance which may endanger health or the environment. Relevant information shall be provided orally or via the current electronic method approved by the Department, within 24 hours from the time the permittee becomes aware of the circumstances, and shall be reported to the appropriate Regional Office during normal business hours or the Environmental Emergency Response hotline at 573-634-2436 outside of normal business hours. A written submission shall also be provided within five (5) business days of the time the permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.



- b. The following shall be included as information which must be reported within 24 hours under this paragraph.
 - i. Any unanticipated bypass which exceeds any effluent limitation in the permit.
 - ii. Any upset which exceeds any effluent limitation in the permit.
 - Violation of a maximum daily discharge limitation for any of the pollutants listed by the Department in the permit required to be reported within 24 hours.
- c. The Department may waive the written report on a case-by-case basis for reports under paragraph 2. b. of this section if the oral report has been received within 24 hours.
- 3. Anticipated Noncompliance. The permittee shall give advance notice to the Department of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements. The notice shall be submitted to the Department 60 days prior to such changes or activity.
- 4. Compliance Schedules. Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date. The report shall provide an explanation for the instance of noncompliance and a proposed schedule or anticipated date, for achieving compliance with the compliance schedule requirement.
- 5. **Other Noncompliance.** The permittee shall report all instances of noncompliance not reported under paragraphs 2, 3, and 6 of this section, at the time monitoring reports are submitted. The reports shall contain the information listed in paragraph 2. a. of this section.
- 6. **Other Information**. Where the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Department, it shall promptly submit such facts or information.

7. Discharge Monitoring Reports.

- a. Monitoring results shall be reported at the intervals specified in the permit.
- b. Monitoring results must be reported to the Department via the current method approved by the Department, unless the permittee has been granted a waiver from using the method. If the permittee has been granted a waiver, the permittee must use forms provided by the Department.
- c. Monitoring results shall be reported to the Department no later than the 28^{th} day of the month following the end of the reporting period.

Section C - Bypass/Upset Requirements

1. Definitions.

- a. *Bypass*: the intentional diversion of waste streams from any portion of a treatment facility, except in the case of blending.
- b. Severe Property Damage: substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
- c. *Upset:* an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

2. Bypass Requirements.

a. Bypass not exceeding limitations. The permittee may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of paragraphs 2. b. and 2. c. of this section.

- b. Notice.
 - i. Anticipated bypass. If the permittee knows in advance of the need for a bypass, it shall submit prior notice, if possible at least 10 days before the date of the bypass.
 - Unanticipated bypass. The permittee shall submit notice of an unanticipated bypass as required in Section B – Reporting Requirements, paragraph 5 (24-hour notice).
- c. Prohibition of bypass.
 - i. Bypass is prohibited, and the Department may take enforcement action against a permittee for bypass, unless:
 - 1. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
 - 2. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and
 - 3. The permittee submitted notices as required under paragraph 2. b. of this section.
 - ii. The Department may approve an anticipated bypass, after considering its adverse effects, if the Department determines that it will meet the three (3) conditions listed above in paragraph 2. c. i. of this section.

3. Upset Requirements.

- a. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of paragraph 3. b. of this section are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review.
- b. Conditions necessary for a demonstration of upset. A permittee who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
 - i. An upset occurred and that the permittee can identify the cause(s) of the upset;
 - ii. The permitted facility was at the time being properly operated; and
 - iii. The permittee submitted notice of the upset as required in Section B

 Reporting Requirements, paragraph 2. b. ii. (24-hour notice).
 iv. The permittee complied with any remedial measures required under
 - iv. The permittee complied with any remedial measures required under Section D – Administrative Requirements, paragraph 4.
- c. Burden of proof. In any enforcement proceeding, the permittee seeking to establish the occurrence of an upset has the burden of proof.

Section D - Administrative Requirements

- 1. **Duty to Comply.** The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Missouri Clean Water Law and Federal Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.
 - a. The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
 - b. The Federal Clean Water Act provides that any person who violates section 301, 302, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any such sections in a permit issued under section 402, or any requirement imposed in a pretreatment program approved under sections 402(a)(3) or 402(b)(8) of the Act, is subject to a civil penalty not to exceed \$25,000 per day for each violation. The Federal Clean Water Act provides that any person who negligently violates sections 301, 302, 306, 307, 308, 318, or 405 of the Act, or any condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, or any requirement



imposed in a pretreatment program approved under section 402(a)(3) or 402(b)(8) of the Act, is subject to criminal penalties of \$2,500 to \$25,000 per day of violation, or imprisonment of not more than one (1) year, or both. In the case of a second or subsequent conviction for a negligent violation, a person shall be subject to criminal penalties of not more than \$50,000 per day of violation, or by imprisonment of not more than two (2) years, or both. Any person who knowingly violates such sections, or such conditions or limitations is subject to criminal penalties of \$5,000 to \$50,000 per day of violation, or imprisonment for not more than three (3) years, or both. In the case of a second or subsequent conviction for a knowing violation, a person shall be subject to criminal penalties of not more than \$100,000 per day of violation, or imprisonment of not more than six (6) years, or both. Any person who knowingly violates section 301, 302, 303, 306, 307, 308, 318 or 405 of the Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of the Act, and who knows at that time that he thereby places another person in imminent danger of death or serious bodily injury, shall, upon conviction, be subject to a fine of not more than \$250,000 or imprisonment of not more than 15 years, or both. In the case of a second or subsequent conviction for a knowing endangerment violation, a person shall be subject to a fine of not more than \$500,000 or by imprisonment of not more than 30 years, or both. An organization, as defined in section 309(c)(3)(B)(iii) of the CWA, shall, upon conviction of violating the imminent danger provision, be subject to a fine of not more than \$1,000,000 and can be fined up to \$2,000,000 for second or subsequent convictions.

- c. Any person may be assessed an administrative penalty by the EPA Director for violating section 301, 302, 306, 307, 308, 318 or 405 of this Act, or any permit condition or limitation implementing any of such sections in a permit issued under section 402 of this Act. Administrative penalties for Class I violations are not to exceed \$10,000 per violation, with the maximum amount of any Class I penalty assessed not to exceed \$25,000. Penalties for Class II violations are not to exceed \$10,000 per day for each day during which the violation continues, with the maximum amount of any Class II penalty not to exceed \$125,000.
- It is unlawful for any person to cause or permit any discharge of water d. contaminants from any water contaminant or point source located in Missouri in violation of sections 644.006 to 644.141 of the Missouri Clean Water Law, or any standard, rule or regulation promulgated by the commission. In the event the commission or the director determines that any provision of sections 644.006 to 644.141 of the Missouri Clean Water Law or standard, rules, limitations or regulations promulgated pursuant thereto, or permits issued by, or any final abatement order, other order, or determination made by the commission or the director, or any filing requirement pursuant to sections 644.006 to 644.141 of the Missouri Clean Water Law or any other provision which this state is required to enforce pursuant to any federal water pollution control act, is being, was, or is in imminent danger of being violated, the commission or director may cause to have instituted a civil action in any court of competent jurisdiction for the injunctive relief to prevent any such violation or further violation or for the assessment of a penalty not to exceed \$10,000 per day for each day, or part thereof, the violation occurred and continues to occur, or both, as the court deems proper. Any person who willfully or negligently commits any violation in this paragraph shall, upon conviction, be punished by a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than one year, or both. Second and successive convictions for violation of the same provision of this paragraph by any person shall be punished by a fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two (2) years, or both.

2. Duty to Reapply.

- a. If the permittee wishes to continue an activity regulated by this permit after the expiration date of this permit, the permittee must apply for and obtain a new permit.
- b. A permittee with a currently effective site-specific permit shall submit an application for renewal at least 180 days before the expiration date of the existing permit, unless permission for a later date has been granted by the Department. (The Department shall not grant permission

for applications to be submitted later than the expiration date of the existing permit.)

- c. A permittees with currently effective general permit shall submit an application for renewal at least 30 days before the existing permit expires, unless the permittee has been notified by the Department that an earlier application must be made. The Department may grant permission for a later submission date. (The Department shall not grant permission for applications to be submitted later than the expiration date of the existing permit.)
- 3. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.
- 4. **Duty to Mitigate.** The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.
- 5. Proper Operation and Maintenance. The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems which are installed by a permittee only when the operation is necessary to achieve compliance with the conditions of the permit.

6. Permit Actions.

- a. Subject to compliance with statutory requirements of the Law and Regulations and applicable Court Order, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:
 - i. Violations of any terms or conditions of this permit or the law;ii. Having obtained this permit by misrepresentation or failure to
 - disclose fully any relevant facts; iii. A change in any circumstances or conditions that requires either a
 - temporary or permanent reduction or elimination of the authorized discharge; or
 - iv. Any reason set forth in the Law or Regulations.
- b. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.

7. Permit Transfer.

- a. Subject to 10 CSR 20-6.010, an operating permit may be transferred upon submission to the Department of an application to transfer signed by the existing owner and the new owner, unless prohibited by the terms of the permit. Until such time the permit is officially transferred, the original permittee remains responsible for complying with the terms and conditions of the existing permit.
- b. The Department may require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the Missouri Clean Water Law or the Federal Clean Water Act.
- c. The Department, within 30 days of receipt of the application, shall notify the new permittee of its intent to revoke or reissue or transfer the permit.
- 8. **Toxic Pollutants.** The permittee shall comply with effluent standards or prohibitions established under section 307(a) of the Federal Clean Water Act for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the Federal Clean Water Act within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if the permit has not yet been modified to incorporate the requirement.
- 9. **Property Rights.** This permit does not convey any property rights of any sort, or any exclusive privilege.



- 10. **Duty to Provide Information.** The permittee shall furnish to the Department, within a reasonable time, any information which the Department may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The permittee shall also furnish to the Department upon request, copies of records required to be kept by this permit.
- 11. **Inspection and Entry.** The permittee shall allow the Department, or an authorized representative (including an authorized contractor acting as a representative of the Department), upon presentation of credentials and other documents as may be required by law, to:
 - Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of the permit;
 - b. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
 - c. Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
 - d. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Federal Clean Water Act or Missouri Clean Water Law, any substances or parameters at any location.

12. Closure of Treatment Facilities.

- Persons who cease operation or plan to cease operation of waste, wastewater, and sludge handling and treatment facilities shall close the facilities in accordance with a closure plan approved by the Department.
- b. Operating Permits under 10 CSR 20-6.010 or under 10 CSR 20-6.015 are required until all waste, wastewater, and sludges have been disposed of in accordance with the closure plan approved by the Department and any disturbed areas have been properly stabilized. Disturbed areas will be considered stabilized when perennial vegetation, pavement, or structures using permanent materials cover all areas that have been disturbed. Vegetative cover, if used, shall be at least 70% plant density over 100% of the disturbed area.

13. Signatory Requirement.

- a. All permit applications, reports required by the permit, or information requested by the Department shall be signed and certified. (See 40 CFR 122.22 and 10 CSR 20-6.010)
- b. The Federal Clean Water Act provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than six (6) months per violation, or by both.
- c. The Missouri Clean Water Law provides that any person who knowingly makes any false statement, representation or certification in any application, record, report, plan, or other document filed or required to be maintained pursuant to sections 644.006 to 644.141 shall, upon conviction, be punished by a fine of not more than ten thousand dollars, or by imprisonment for not more than six months, or by both.
- 14. **Severability.** The provisions of the permit are severable, and if any provision of the permit, or the application of any provision of the permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of the permit, shall not be affected thereby.



STANDARD CONDITIONS FOR NPDES PERMITS ISSUED BY THE MISSOURI DEPARTMENT OF NATURAL RESOURCES MISSOURI CLEAN WATER COMMISSION REVISED MAY 1, 2013

PART II - SPECIAL CONDITIONS – PUBLICLY OWNED TREATMENT WORKS SECTION A – INDUSTRIAL USERS

1. Definitions

Definitions as set forth in the Missouri Clean Water Laws and approved by the Missouri Clean Water Commission shall apply to terms used herein.

Significant Industrial User (SIU). Except as provided in the *General Pretreatment Regulation* 10 CSR 20-6.100, the term Significant Industrial User means:

- 1. All Industrial Users subject to Categorical Pretreatment Standards; and
- 2. Any other Industrial User that: discharges an average of 25,000 gallons per day or more of process wastewater to the Publicly-Owned Treatment Works (POTW) (excluding sanitary, noncontact cooling and boiler blowdown wastewater); contributes a process wastestream which makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the POTW treatment plant; or is designated as such by the Control Authority on the basis that the Industrial User has a reasonable potential for adversely affecting the POTW's or for violating any Pretreatment Standard or requirement.

Clean Water Act (CWA) is the the federal Clean Water Act of 1972, 33 U.S.C. § 1251 et seq. (2002).

2. Identification of Industrial Discharges

Pursuant to 40 CFR 122.44(j)(1), all POTWs shall identify, in terms of character and volume of pollutants, any Significant Industrial Users discharging to the POTW subject to Pretreatment Standards under section 307(b) of the CWA and 40 CFR 403.

3. Application Information

Applications for renewal or modification of this permit must contain the information about industrial discharges to the POTW pursuant to 40 CFR 122.21(j)(6)

4. Notice to the Department

Pursuant to 40 CFR 122.42(b), all POTWs must provide adequate notice of the following:

- Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to section 301 or 306 of CWA if it were directly discharging these pollutants; and
- 2. Any substantial change into the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit.
- 3. For purposes of this paragraph, adequate notice shall include information on:
 - i. the quality and quantity of effluent introduced into the POTW, and
 - ii. any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

For POTWs without an approved pretreatment program, the notice of industrial discharges which was not included in the permit application shall be made as soon as practicable. For POTWs with an approved pretreatment program, notice is to be included in the annual pretreatment report required in the special conditions of this permit. Notice may be sent to:

> Missouri Department of Natural Resources Water Protection Program Attn: Pretreatment Coordinator P.O. Box 176 Jefferson City, MO 65102

STANDARD CONDITIONS FOR NPDES PERMITS ISSUED BY THE MISSOURI DEPARTMENT OF NATURAL RESOURCES MISSOURI CLEAN WATER COMMISSION March 1, 2015

PART III – SLUDGE AND BIOSOLIDS FROM DOMESTIC AND INDUSTRIAL WASTEWATER TREATMENT FACILITIES

SECTION A – GENERAL REQUIREMENTS

- This permit pertains to sludge requirements under the Missouri Clean Water Law and regulation for domestic
 wastewater and industrial process wastewater. This permit also incorporates applicable federal sludge disposal
 requirements under 40 CFR 503 for domestic wastewater. The Environmental Protection Agency (EPA) has principal
 authority for permitting and enforcement of the federal sludge regulations under 40 CFR 503 for domestic wastewater.
 EPA has reviewed and accepted these standard sludge conditions. EPA may choose to issue a separate sludge
 addendum to this permit or a separate federal sludge permit at their discretion to further address the federal
 requirements.
- These PART III Standard Conditions apply only to sludge and biosolids generated at domestic wastewater treatment facilities, including public owned treatment works (POTW), privately owned facilities and sludge or biosolids generated at industrial facilities.
- 3. Sludge and Biosolids Use and Disposal Practices:
 - a. The permittee is authorized to operate the sludge and biosolids treatment, storage, use, and disposal facilities listed in the facility description of this permit.
 - b. The permittee shall not exceed the design sludge volume listed in the facility description and shall not use sludge disposal methods that are not listed in the facility description, without prior approval of the permitting authority.
 - c. The permittee is authorized to operate the storage, treatment or generating sites listed in the Facility Description section of this permit.
- 4. Sludge Received from other Facilities:
 - a. Permittees may accept domestic wastewater sludge from other facilities including septic tank pumpings from residential sources as long as the design sludge volume is not exceeded and the treatment facility performance is not impaired.
 - b. The permittee shall obtain a signed statement from the sludge generator or hauler that certifies the type and source of the sludge
- 5. These permit requirements do not supersede nor remove liability for compliance with county and other local ordinances.
- 6. These permit requirements do not supersede nor remove liability for compliance with other environmental regulations such as odor emissions under the Missouri Air Pollution Control Law and regulations.
- This permit may (after due process) be modified, or alternatively revoked and reissued, to comply with any applicable sludge disposal standard or limitation issued or approved under Section 405(d) of the Clean Water Actor under Chapter 644 RSMo.
- 8. In addition to STANDARD CONDITIONS, the Department may include sludge limitations in the special conditions portion or other sections of a site specific permit.
- 9. Alternate Limits in the Site Specific Permit.
 - Where deemed appropriate, the Department may require an individual site specific permit in order to authorize alternate limitations:
 - a. A site specific permit must be obtained for each operating location, including application sites.
 - b. To request a site specific permit, an individual permit application, permit fee, and supporting documents shall be submitted for each operating location. This shall include a detailed sludge/biosolids management plan or engineering report.
- 10. Exceptions to these Standard Conditions may be authorized on a case-by-case basis by the Department, as follows:
 - a. The Department will prepare a permit modification and follow permit notice provisions as applicable under 10 CSR 20-6.020, 40 CFR 124.10, and 40 CFR 501.15(a)(2)(ix)(E). This includes notification of the owner of the property located adjacent to each land application site, where appropriate.
 - b. Exceptions cannot be granted where prohibited by the federal sludge regulations under 40 CFR 503.

SECTION B – DEFINITIONS

- 1. Best Management Practices include agronomic loading rates, soil conservation practices and other site restrictions.
- 2. Biosolids means organic fertilizer or soil amendment produced by the treatment of domestic wastewater sludge.
- 3. Biosolids land application facility is a facility where biosolids are spread onto the land at agronomic rates for production of food or fiber. The facility includes any structures necessary to store the biosolids until soil, weather, and crop conditions are favorable for land application.
- 4. Class A biosolids means a material that has met the Class A pathogen reduction requirements or equivalent treatment by a Process to Further Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
- 5. Class B biosolids means a material that has met the Class B pathogen reduction requirements or equivalent treatment by a Process to Significantly Reduce Pathogens (PFRP) in accordance with 40 CFR 503.
- 6. Domestic wastewater means wastewater originating from the sanitary conveniences of residences, commercial buildings, factories and institutions; or co-mingled sanitary and industrial wastewater processed by a (POTW) or a privately owned facility.
- 7. Industrial wastewater means any wastewater, also known as process water, not defined as domestic wastewater. Per 40 CFR Part 122, process water means any water which, during manufacturing or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct, or waste product.
- 8. Mechanical treatment plants are wastewater treatment facilities that use mechanical devices to treat wastewater, including septic tanks, sand filters, extended aeration, activated sludge, contact stabilization, trickling filters, rotating biological discs, and other similar facilities. It does not include wastewater treatment lagoons and constructed wetlands for wastewater treatment.
- 9. Operating location as defined in 10 CSR 20-2.010 is all contiguous lands owned, operated or controlled by one (1) person or by two (2) or more persons jointly or as tenants in common.
- 10. Plant Available Nitrogen (PAN) is the nitrogen that will be available to plants during the growing seasons after biosolids application.
- 11. Public contact site is land with a high potential for contact by the public. This includes, but is not limited to, public parks, ball fields, cemeteries, plant nurseries, turf farms, and golf courses.
- 12. Sludge is the solid, semisolid, or liquid residue removed during the treatment of wastewater. Sludge includes septage removed from septic tanks or equivalent facilities. Sludge does not include carbon coal byproducts (CCBs)
- 13. Sludge lagoon is part of a mechanical wastewater treatment facility. A sludge lagoon is an earthen basin that receives sludge that has been removed from a wastewater treatment facility. It does not include a wastewater treatment lagoon or sludge treatment units that are not a part of a mechanical wastewater treatment facility.
- 14. Septage is the material pumped from residential septic tanks and similar treatment works (with a design population of less than 150 people). The standard for biosolids from septage is different from other sludges.

SECTION C – MECHANICAL WASTEWATER TREATMENT FACILITIES

- 1. Sludge shall be routinely removed from wastewater treatment facilities and handled according to the permit facility description and sludge conditions of this permit.
- 2. The permittee shall operate the facility so that there is no sludge discharged to waters of the state.
- Mechanical treatment plants shall have separate sludge storage compartments in accordance with 10 CSR 20, Chapter 8. Failure to remove sludge from these storage compartments on the required design schedule is a violation of this permit.

SECTION D - SLUDGE DISPOSED AT OTHER TREATMENT FACILITY OR CONTRACT HAULER

- 1. This section applies to permittees that haul sludge to another treatment facility for disposal or use contract haulers to remove and dispose of sludge.
- 2. Permittees that use contract haulers are responsible for compliance with all the terms of this permit including final disposal, unless the hauler has a separate permit for sludge or biosolids disposal issued by the Department; or the hauler transports the sludge to another permitted treatment facility.
- 3. Haulers who land apply septage must obtain a state permit.
- 4. Testing of sludge, other than total solids content, is not required if sludge is hauled to a municipal wastewater treatment facility or other permitted wastewater treatment facility, unless it is required by the accepting facility.

SECTION E - INCINERATION OF SLUDGE

- 1. Sludge incineration facilities shall comply with the requirements of 40 CFR 503 Subpart E; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
- 2. Permittee may be authorized under the facility description of this permit to store incineration ash in lagoons or ash ponds. This permit does not authorize the disposal of incineration ash. Incineration ash shall be disposed in accordance with 10 CSR 80; or if the ash is determined to be hazardous with 10 CSR 25.
- 3. In addition to normal sludge monitoring, incineration facilities shall report the following as part of the annual report, quantity of sludge incinerated, quantity of ash generated, quantity of ash stored, and ash used or disposal method, quantity, and location. Permittee shall also provide the name of the disposal facility and the applicable permit number.

SECTION F - SURFACE DISPOSAL SITES AND SLUDGE LAGOONS

- 1. Surface disposal sites of domestic facilities shall comply with the requirements in 40 CFR 503 Subpart C; air pollution control regulations under 10 CSR 10; and solid waste management regulations under 10 CSR 80.
- 2. Sludge storage lagoons are temporary facilities and are not required to obtain a permit as a solid waste management facility under 10 CSR 80. In order to maintain sludge storage lagoons as storage facilities, accumulated sludge must be removed routinely, but not less than once every two years unless an alternate schedule is approved in the permit. The amount of sludge removed will be dependent on sludge generation and accumulation in the facility. Enough sludge must be removed to maintain adequate storage capacity in the facility.
 - a. In order to avoid damage to the lagoon seal during cleaning, the permittee may leave a layer of sludge on the bottom of the lagoon, upon prior approval of the Department; or
 - b. Permittee shall close the lagoon in accordance with Section H.

SECTION G - LAND APPLICATION

- 1. The permittee shall not land apply sludge or biosolids unless land application is authorized in the facility description or the special conditions of the issued NPDES permit.
- 2. Land application sites within a 20 miles radius of the wastewater treatment facility are authorized under this permit when biosolids are applied for beneficial use in accordance with these standard conditions unless otherwise specified in a site specific permit. If the permittee's land application site is greater than a 20 mile radius of the wastewater treatment facility, approval must be granted from the Department.
- 3. Land application shall not adversely affect a threatened or endangered species or its designated critical habitat.
- 4. Biosolids shall not be applied unless authorized in this permit or exempted under 10 CSR 20, Chapter 6.
 - a. This permit does not authorize the land application of domestic sludge except for when sludge meets the definition of biosolids.
 - b. This permit authorizes "Class A or B" biosolids derived from domestic wastewater and/or process water sludge to be land applied onto grass land, crop land, timber or other similar agricultural or silviculture lands at rates suitable for beneficial use as organic fertilizer and soil conditioner.
- 5. Public Contact Sites:

Permittees who wish to apply Class A biosolids to public contact sites must obtain approval from the Department after two years of proper operation with acceptable testing documentation that shows the biosolids meet Class A criteria. A shorter length of testing will be allowed with prior approval from the Department. Authorization for land applications must be provided in the special conditions section of this permit or in a separate site specific permit.

- a. After Class B biosolids have been land applied, public access must be restricted for 12 months.
- b. Class B biosolids are only land applied to root crops, home gardens or vegetable crops whose edible parts will not be for human consumption.
- 6. Agricultural and Silvicultural Sites:

Septage - Based on Water Quality guide 422 (WQ422) published by the University of Missouri

- a. Haulers that land apply septage must obtain a state permit
- b. Do not apply more than 30,000 gallons of septage per acre per year.
- c. Septage tanks are designed to retain sludge for one to three years which will allow for a larger reduction in pathogens and vectors, as compared to other mechanical type treatment facilities.
- d. To meet Class B sludge requirements, maintain septage at 12 pH for at least thirty (30) minutes before land application. 50 pounds of hydrated lime shall be added to each 1,000 gallons of septage in order to meet pathogen and vector stabilization for septage biosolids applied to crops, pastures or timberland.
- e. Lime is to be added to the pump truck and not directly to the septic tanks, as lime would harm the beneficial bacteria of the septic tank.

Biosolids - Based on Water Quality guide 423, 424, and 425 (WQ423, WQ424, WQ425) published by the University of Missouri;

- a. Biosolids shall be monitored to determine the quality for regulated pollutants
- b. The number of samples taken is directly related to the amount of sludge produced by the facility (See Section I of these Standard Conditions). Report as dry weight unless otherwise specified in the site specific permit. Samples should be taken only during land application periods. When necessary, it is permissible to mix biosolids with lower concentrations of biosolids as well as other suitable Department approved material to reach the maximum concentration of pollutants allowed.
- c. Table 1 gives the maximum concentration allowable to protect water quality standards

TABLE 1		
Biosolids ceiling concentration ¹		
Pollutant	Milligrams per kilogram dry weight	
Arsenic	75	
Cadmium	85	
Copper	4,300	
Lead	840	
Mercury	57	
Molybdenum	75	
Nickel	420	
Selenium	100	
Zinc	7,500	

¹ Land application is not allowed if the sludge concentration exceeds the maximum limits for any of these pollutants

d. The low metal concentration biosolids has reduced requirements because of its higher quality and can safely be applied for 100 years or longer at typical agronomic loading rates. (See Table 2)

TABLE 2				
Biosolids Low Metal Concentration ¹				
Pollutant	Milligrams per kilogram dry weight			
Arsenic	41			
Cadmium	39			
Copper	1,500			
Lead	300			
Mercury	17			
Nickel	420			
Selenium	36			
Zinc	2,800			

You may apply low metal biosolids without tracking cumulative metal limits, provided the cumulative application of biosolids does not exceed 500 dry tons per acre.

e. Each pollutant in Table 3 has an annual and a total cumulative loading limit, based on the allowable pounds per acre for various soil categories.

TABLE 3						
D 11 4 4	CEC 15+		CEC 5 to 15		CEC 0 to 5	
Pollutant	Annual	Total ¹	Annual	Total ¹	Annual	Total ¹
Arsenic	1.8	36.0	1.8	36.0	1.8	36.0
Cadmium	1.7	35.0	0.9	9.0	0.4	4.5
Copper	66.0	1,335.0	25.0	250.0	12.0	125.0
Lead	13.0	267.0	13.0	267.0	13.0	133.0
Mercury	0.7	15.0	0.7	15.0	0.7	15.0
Nickel	19.0	347.0	19.0	250.0	12.0	125.0
Selenium	4.5	89.0	4.5	44.0	1.6	16.0
Zinc	124.0	2,492.0	50.0	500.0	25.0	250.0

¹ Total cumulative loading limits for soils with equal or greater than 6.0 pH (salt based test) or 6.5 pH (water based test)

4

TABLE 4 - Guidelines	for land application of other trace substances ¹	

Cumulat	ive Loading	
Pollutant	Pounds per acre	
Aluminum	$4,000^2$	
Beryllium	100	
Cobalt	50	
Fluoride	800	
Manganese	500	
Silver	200	
Tin	1,000	
Dioxin	$(10 \text{ ppt in soil})^3$	
Other	4	

¹ Design of land treatment systems for Industrial Waste, 1979. Michael Ray Overcash, North Carolina State University and Land Treatment of Municipal Wastewater, EPA 1981.)

- ² This applies for a soil with a pH between 6.0 and 7.0 (salt based test) or a pH between 6.5 to 7.5 (water based test). Case-by-case review is required for higher pH soils.
- ³ Total Dioxin Toxicity Equivalents (TEQ) in soils, based on a risk assessment under 40 CFR 744, May 1998.
- ⁴ Case by case review. Concentrations in sludge should not exceed the 95th percentile of the National Sewage Sludge Survey, EPA, January 2009.

Best Management Practices - Based on Water Quality guide 426 (WQ426) published by the University of Missouri

- a. Use best management practices when applying biosolids.
- b. Biosolids cannot discharge from the land application site
- c. Biosolid application is subject to the Missouri Department of Agriculture State Milk Board concerning grazing restrictions of lactating dairy cattle.
- d. Biosolid application must be in accordance with section 4 of the Endangered Species Act.
- e. Do not apply more than the agronomic rate of nitrogen needed.
- f. The applicator must document the Plant Available Nitrogen (PAN) loadings, available nitrogen in the soil, and crop removal when either of the following occurs: 1) When biosolids are greater than 50,000 mg/kg TN; or 2) When biosolids are land applied at an application rate greater than two dry tons per acre per year.
 - i. PAN can be determined as follows and is in accordance with WQ426
 - (Nitrate + nitrite nitrogen) + (organic nitrogen x 0.2) + (ammonia nitrogen x volatilization factor¹). ¹Volatilization factor is 0.7 for surface application and 1 for subsurface application.
- g. Buffer zones are as follows:
 - i. 300 feet of a water supply well, sinkhole, lake, pond, water supply reservoir or water supply intake in a stream;
 - 300 feet of a losing stream, no discharge stream, stream stretches designated for whole body contact recreation, wild and scenic rivers, Ozark National Scenic Riverways or outstanding state resource waters as listed in the Water Quality Standards, 10 CSR 20-7.031;
 - iii. 150 feet if dwellings;
 - iv. 100 feet of wetlands or permanent flowing streams;
 - v. 50 feet of a property line or other waters of the state, including intermittent flowing streams.
- h. Slope limitation for application sites are as follows;
 - i. A slope 0 to 6 percent has no rate limitation
 - ii. Applied to a slope 7 to 12 percent, the applicator may apply biosolids when soil conservation practices are used to meet the minimum erosion levels
 - Slopes > 12 percent, apply biosolids only when grass is vegetated and maintained with at least 80 percent ground cover at a rate of two dry tons per acre per year or less.
- i. No biosolids may be land applied in an area that it is reasonably certain that pollutants will be transported into waters of the state.
- j. Do not apply biosolids to sites with soil that is snow covered, frozen or saturated with liquid without prior approval by the Department.
- k. Biosolids / sludge applicators must keep detailed records up to five years.

SECTION H - CLOSURE REQUIREMENTS

- 1. This section applies to all wastewater facilities (mechanical, industrial, and lagoons) and sludge or biosolids storage and treatment facilities and incineration ash ponds. It does not apply to land application sites.
- 2. Permittees of a domestic wastewater facility who plan to cease operation must obtain Department approval of a closure plan which addresses proper removal and disposal of all residues, including sludge, biosolids. Mechanical plants, sludge lagoons, ash ponds and other storage structures must obtain approval of a closure plan from the Department. Permittee must maintain this permit until the facility is closed in accordance with the approved closure plan per 10 CSR 20 6.010 and 10 CSR 20 6.015.
- 3. Residuals that are left in place during closure of a lagoon or earthen structure or ash pond shall not exceed the agricultural loading rates as follows:
 - a. Residuals shall meet the monitoring and land application limits for agricultural rates as referenced in Section H of these standard conditions.
 - b. If a wastewater treatment lagoon has been in operation for 15 years or more without sludge removal, the sludge in the lagoon qualifies as a Class B biosolids with respect to pathogens due to anaerobic digestion, and testing for fecal coliform is not required. For other lagoons, testing for fecal coliform is required to show compliance with Class B biosolids limitations. In order to reach Class B biosolids requirements, fecal coliform must be less than 2,000,000 colony forming units or 2,000,000 most probable number. All fecal samples must be presented as geometric mean per gram.
 - c. The allowable nitrogen loading that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. For a grass cover crop, the allowable PAN is 300 pounds/acre.
 - i. PAN can be determined as follows:
 - (Nitrate + nitrite nitrogen) + (organic nitrogen x 0.2) + (ammonia nitrogen x volatilization factor¹). ¹Volatilization factor is 0.7 for surface application and 1 for subsurface application.
- 4. When closing a domestic wastewater treatment lagoon with a design treatment capacity equal or less than 150 persons, the residuals are considered "septage" under the similar treatment works definition. See Section B of these standard conditions. Under the septage category, residuals may be left in place as follows:
 - a. Testing for metals or fecal coliform is not required
 - b. If the wastewater treatment lagoon has been in use for less than 15 years, mix lime with the sludge at a rate of 50 pounds of hydrated lime per 1000 gallons (134 cubic feet) of sludge.
 - c. The amount of sludge that may be left in the lagoon shall be based on the plant available nitrogen (PAN) loading. 100 dry tons/acre of sludge may be left in the basin without testing for nitrogen. If 100 dry tons/acre or more will be left in the lagoon, test for nitrogen and determine the PAN using the calculation above. Allowable PAN loading is 300 pounds/acre.
- 5. Residuals left within the domestic lagoon shall be mixed with soil on at least a 1 to 1 ratio, the lagoon berm shall be demolished, and the site shall be graded and contain ≥70% vegetative density over 100% of the site so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
- 6. Lagoons and/or earthen structure and/or ash pond closure activities shall obtain a storm water permit for land disturbance activities that equal or exceed one acre in accordance with 10 CSR 20-6.200
- When closing a mechanical wastewater and/or industrial process wastewater plant; all sludge must be cleaned out and disposed of in accordance with the Department approved closure plan before the permit for the facility can be terminated.
 - a. Land must be stabilized which includes any grading, alternate use or fate upon approval by the Department, remediation, or other work that exposes sediment to stormwater per 10 CSR 20-6.200. The site shall be graded and contain ≥70% vegetative density over 100% of the site, so as to avoid ponding of storm water and provide adequate surface water drainage without creating erosion.
 - Per 10 CSR 20-6.015(4)(B)6, Hazardous Waste shall not be land applied or disposed during industrial and mechanical plant closures unless in accordance with Missouri Hazardous Waste Management Law and Regulations under 10 CSR 25.
 - c. After demolition of the mechanical plant / industrial plant, the site must only contain clean fill defined in RSMo 260.200 (5) as uncontaminated soil, rock, sand, gravel, concrete, asphaltic concrete, cinderblocks, brick, minimal amounts of wood and metal, and inert solids as approved by rule or policy of the Department for fill or other beneficial use. Other solid wastes must be removed.
- 8. If sludge from the domestic lagoon or mechanical treatment plant exceeds agricultural rates under Section G and/or H, a landfill permit or solid waste disposal permit must be obtained if the permittee chooses to seek authorization for on-site sludge disposal under the Missouri Solid Waste Management Law and regulations per 10 CSR 80, and the permittee must comply with the surface disposal requirements under 40 CFR 503, Subpart C.

SECTION I – MONITORING FREQUENCY

1. At a minimum, sludge or biosolids shall be tested for volume and percent total solids on a frequency that will accurately represent sludge quantities produced and disposed. Please see the table below.

I ABLE 5					
Design Sludge	Monitoring Frequency (See Notes 1, 2, and 3)				
Production (dry tons per year)	Metals, Pathogens and Vectors	Nitrogen TKN ¹	Nitrogen PAN ²	Priority Pollutants and TCLP ³	
0 to 100	1 per year	1 per year	1 per month	1 per year	
101 to 200	biannual	biannual	1 per month	1 per year	
201 to 1,000	quarterly	quarterly	1 per month	1 per year	
1,001 to 10,000	1 per month	1 per month	1 per week	4	
10,001 +	1 per week	1 per week	1 per day	4	
Test total Vialda	hl nitrogan if higgalide a	autientien is 2 destaure au			

TABLE 5

¹ Test total Kjeldahl nitrogen, if biosolids application is 2 dry tons per acre per year or less.

² Calculate plant available nitrogen (PAN) when either of the following occurs: 1) when biosolids are greater than 50,000 mg/kg TN; or 2) when biosolids are land applied at an application rate greater than two dry tons per acre per year.

³ Priority pollutants (40 CFR 122.21, Appendix D, Tables II and III) and toxicity characteristic leaching procedure (40 CFR 261.24) is required only for permit holders that must have a pre-treatment program.

Note 1: Total solids: A grab sample of sludge shall be tested one per day during land application periods for percent total solids. This data shall be used to calculate the dry tons of sludge applied per acre. Note 2: Total Phosphorus: Total phosphorus and total potassium shall be tested at the same monitoring frequency as metals. Note 3: Table 5 is not applicable for incineration and permit holders that landfill their sludge.

- 2. If you own a wastewater treatment lagoon or sludge lagoon that is cleaned out once a year or less, you may choose to sample only when the sludge is removed or the lagoon is closed. Test one composite sample for each 100 dry tons of sludge or biosolids removed from the lagoon during the year within the lagoon at closing. Composite sample must represent various areas at one-foot depth.
- 3. Additional testing may be required in the special conditions or other sections of the permit. Permittees receiving industrial wastewater may be required to conduct additional testing upon request from the Department.
- 4. At this time, the Department recommends monitoring requirements shall be performed in accordance with, "POTW Sludge Sampling and Analysis Guidance Document," United States Environmental Protection Agency, August 1989, and the subsequent revisions.

SECTION J - RECORD KEEPING AND REPORTING REQUIREMENTS

- 1. The permittee shall maintain records on file at the facility for at least five years for the items listed in these standard conditions and any additional items in the Special Conditions section of this permit. This shall include dates when the sludge facility is checked for proper operation, records of maintenance and repairs and other relevant information.
- 2. Reporting period
 - a. By January 28th of each year, an annual report shall be submitted for the previous calendar year period for all mechanical wastewater treatment facilities, sludge lagoons, and sludge or biosolids disposal facilities.
 - b. Permittees with wastewater treatment lagoons shall submit the above annual report only when sludge or biosolids are removed from the lagoon during the report period or when the lagoon is closed.
- 3. Report Forms. The annual report shall be submitted on report forms provided by the Department or equivalent forms approved by the Department.
- 4. Reports shall be submitted as follows:

Major facilities (those serving 10,000 persons or 1 million gallons per day) shall report to both the Department and EPA. Other facilities need to report only to the Department. Reports shall be submitted to the addresses listed as follows:

DNR regional office listed in your permit (see cover letter of permit) ATTN: Sludge Coordinator EPA Region VII Water Compliance Branch (WACM)

Water Compliance Branch (WACM Sludge Coordinator 11201 Renner Blvd. Lenexa, KS 66219

⁴ One sample for each 1,000 dry tons of sludge.

- 5. Annual report contents. The annual report shall include the following:
 - a. Sludge and biosolids testing performed. Include a copy or summary of all test results, even if not required by the permit.
 - b. Sludge or biosolids quantity shall be reported as dry tons for quantity generated by the wastewater treatment facility, the quantity stored on site at the end of the year, and the quantity used or disposed.
 - c. Gallons and % solids data used to calculate the dry ton amounts.
 - d. Description of any unusual operating conditions.
 - e. Final disposal method, dates, and location, and person responsible for hauling and disposal.
 - i. This must include the name, address for the hauler and sludge facility. If hauled to a municipal wastewater treatment facility, sanitary landfill, or other approved treatment facility, give the name of that facility.
 - ii. Include a description of the type of hauling equipment used and the capacity in tons, gallons, or cubic feet.
 - f. Contract Hauler Activities:

If contract hauler, provide a copy of a signed contract from the contractor. Permittee shall require the contractor to supply information required under this permit for which the contractor is responsible. The permittee shall submit a signed statement from the contractor that he has complied with the standards contained in this permit, unless the contract hauler has a separate sludge or biosolids use permit.

- g. Land Application Sites:
 - i. Report the location of each application site, the annual and cumulative dry tons/acre for each site, and the landowners name and address. The location for each spreading site shall be given as a legal description for nearest ¹/₄, ¹/₄, Section, Township, Range, and county, or UTM coordinates. The facility shall report PAN when either of the following occurs: 1) When biosolids are greater than 50,000 mg/kg TN; or 2) when biosolids are land applied at an application rate greater than two dry tons per acre per year.
 - ii. If the "Low Metals" criteria are exceeded, report the annual and cumulative pollutant loading rates in pounds per acre for each applicable pollutant, and report the percent of cumulative pollutant loading which has been reached at each site.
 - iii. Report the method used for compliance with pathogen and vector attraction requirements.
 - iv. Report soil test results for pH, CEC, and phosphorus. If none was tested during the year, report the last date when tested and results.


	•		RECEIVED	no	0 (1.12) 1.1
MISSOURI DEPARTMENT OF NATURAL RESOURCES WATER PROTECTION PROGRAM, WATER POLLUTION E FORM B – APPLICATION FOR CONSTRUCTION OR OPE FACILITIES WHICH RECEIVE PRIMARILY DOMESTIC WA day) UNDER MISSOURI CLEAN WATER LAW			RATING PERMIT FOR	CHECK	A NUCA (1)6/10 TU RAGENCY USE ONLY NUMBER RECEIVED FEE SUBMITTED
NOTE_	PLEASE READ THE ACCOMPANYING INST	RUCTIONS	BEFORE COMPLETING TH	IS FORM	
	This application is for: An operating permit and antidegradation review p A construction permit following an appropriate op A construction permit and a concurrent operating A construction permit (submitted before Aug. 30, An operating permit for a new or unpermitted faci An operating permit renewal: Permit #MO- <u>01089</u> An operating permit modification: Permit #MO- s this a Federal/State Funded Project?	perating permi permit and a 2008 or antic ility. 295 YES	ntidegradation review public legradation review is not req Construction Perm Expiration Date <u>8/</u> Reason:	notice. uired). nit # (10/11	AP 327Ø
NAME		TRICT		TELEPHO 573-441	NE WITH AREA CODE
ADDRESS (PH	HARTSBURG WWTF/BOONE COUNTY REGIONAL SEWER DISTRICT ADDRESS (PHYSICAL) PO BOX 24, CITY OF HARTSBURG CITY HARTSBURG		STATE MO	ZIP CODE 65039	
2.1 L				BOONE C	County
ŀ		thing (Y): <u>-921</u> th referenced t	18168 o North American Datum 1983	(NAD83)	
3. 0	OWNER				
NAME VILLAGE C	OF HARTSBURG	E	MAIL ADDRESS	TELEPHO 573-441	NE WITH AREA CODE -0098
ADDRESS PO BOX 24	4	HARTSBUR	3	STATE MO	ZIP CODE 65039
3.1 F	Request review of draft permit prior to Public Notic	e?	YES NO		
n	CONTINUING AUTHORITY: Permanent organize maintenance and modernization of the facility.	ation which	will serve as the continuing	g authorit	y for the operation,
NAME BOONE CO	DUNTY REGIONAL SEWER DISTRICT			573-441	SELECTION
ADDRESS 1314 NORT	TH 7 [™] STREET,	CITY COLUMBIA		STATE MO	ZIP CODE 65201-3902
A REAL PROPERTY AND A REAL	OPERATOR				
DWAYNE C	COOKSEY	CERTIFICATE NUMBER		TELEPHONE WITH AREA CODE 573-441-0098	
6. F	ACILITY CONTACT	制作。常山修		C. Carlos	
DWAYNE C	COOKSEY	OPERATOR		TELEPHON 573-441-	NE WITH AREA CODE -0098

7.0	ADDITIONAL FACILITY INFORMATION				
7.1	Description of facilities (Attach additional sheet if required). Attach a 1" = 2,000' scale U.S. Geological Survey topographic map showing location of all outfalls and downstream landowners. (See Item 9.)				
7.2	Facility SIC code: 4952; Discharge SIC code:; Facility NAICS code:; Discharge NAICS code:				
7.3	Number of people presently connected or population equivalent (P.E.) 89 Design P.E. 144				
	Number of units presently connected: Homes 53 Trailers Apartments Other				
1	Design flow for this outfall: <u>14.400 GPD</u> Total design flow for the facility: <u>14.400 GPD</u> Actual flow for this outfall: <u>5.550 GPD</u>				
- Den State	Commercial Establishment: Daily number of employees working Daily number of customers/guests				
7.4	Length of pipe in the sewer collection system? -3000feet/miles (Please denote which unit is appropriate.)				
7.5	Does any bypassing occur in the collection system or at the treatment facility? Yes No (If yes, attach explanation.)				
7.6	Does significant infiltration occur in the collection system? Yes X No (If yes, attach explanation and proposed repair.)				
7.7	Is industrial waste discharged to the facility identified in Item 2? Yes X No (If yes, see instructions.)				
7.8	Will the discharge be continuous through the year?				
	a. Discharge will occur during the following months: ALL				
	b. How many days of the week will the discharge occur? Z				
7.9	Is wastewater land applied?				
7.10	Will chlorine be added to the effluent?				
	a. If chlorine is added, what is the resulting residual? µg/l (micrograms per liter)				
7.11	Does this facility discharge to a losing stream or sinkhole?				
7.12	Attach a flow chart showing all influents, treatment facilities and outfalls.				
7.13	Has a waste load allocation study been completed for this facility? □Yes				
7.14	List all permit violations, including effluent limit exceedances in the last five years. Attach a separate sheet if necessary.				
	If none, write none. NONE				
MO 780-	1512 (09-08)				

*

8.	SLUDGE HANDLING, USE AND DISPOSAL			
8.1	Is the sludge a hazardous waste as defined by 10	CSR 25? Yes No		
8.2	Sludge Production, including sludge received from others: 2.2 Design Dry Tons/Year Actual Dry Tons/Year			
8.3	Capacity of sludge holding structures:			
	Sludge storage provided: cubic feet;	; days of storage; average	e percent sol	ids of sludge;
	No sludge storage is provided.			
8.4	Type of Storage: Holding tank	Building		
	🔲 Basin	Other (Please describe))	
	Concrete Pad			
8.5	Sludge Treatment:			
0.77298.943	Anaerobic Digester 🛛 Lagoon	Composting		
	□ Storage Tank □ Aerobic Diges	ster 🗌 Other (Attach descri	ption)	
	Lime Stabilization Air or Heat Dr			
8.6	Sludge Use or Disposal:			
		osal (Sludge Disposal Lagoon, Sludge I	held for more	than two years)
	Contract Hauler Incineration			
		ned in Wastewater treatment lagoon		
		Attach explanation sheet.		
	Solid Waste Landfill		9	
8.7	PERSON RESPONSIBLE FOR HAULING SLUD	GE TO DISPOSAL FACILITY		
	By Applicant By Others (co	(THEN THE THE THE CONTROL THE SECTION OF THE		
NAME				
C ALTONOMICS				
ADDRESS		CITY	STATE	ZIP CODE
CONTINT	DEDOON.			
CONTACT	PERSON	TELEPHONE WITH AREA CODE	PERMIT NO MO-	D.
8.8			WIC	
0.0	SLUDGE USE OR DISPOSAL FACILITY By Applicant By Others (Please	complete below)		
NAME		complete below.)		
ADDRESS		CITY	STATE	ZIP CODE
0.01.01.07				
CONTACT	PERSON	TELEPHONE WITH AREA CODE	PERMIT NO	D.
8.9	Does the sludge or biosolids disposal comply with	federal cludge regulations under 40 Cl	1100470	
0.9	Yes No (Please attach explanation)	rederal sludge regulations under 40 Ch	FN 303?	
0	DOWNSTREAM LANDOWNER (S). ATTACH AD	DITIONAL CHEETS AS NECESSAR		DUCTIONS
9. NAME		DITIONAL SHEETS AS NECESSAR	. SEE INST	AUCTIONS.
(Carl J. Graessle			
ADDRESS	457 County Road 394	CITY II a lal	STATE	ZIP CODE
		Hartsburg	MO	65039
10.	DRINKING WATER SUPPLY INFORMATION			
10.1	WHAT IS THE SOURCE OF YOUR DRINKING W			
	A. Public supply (municipal or water district water			
	If public, please give name of the public supp	IV BOONE COUNTY CONSOLIDATED	<u>) PWSD #1</u>	
	B. Private wellC. Surface water (lake, pond or stream)			
10.2	Does your drinking water source serve at least 25	people at least 60 days per year (not n	ecessarily co	nsecutive days)?
	Yes 🗋 No			
10.3	Does your supply serve housing which is occupied	d year round by the same people? This	does not inc	lude housing which is
	occupied seasonally? Xes INO			•
11.	L certify that I am familiar with the information cont	ained in the application, that to the bes	t of my knowle	edge and helief such
11. I certify that I am familiar with the information contained in the application, that to the best of my knowledge and belief such information is true, complete and accurate, and if granted this permit, I agree to abide by the Missouri Clean Water Law and				
	all rules, regulations, orders and decisions, subject to any legitimate appeal available to applicant under the Missouri Clean			
	Water Law.			
NAME AND	OFFICIAL TITLE (TYPE OR PRINT)		TELEPHONE WITH	
R.		пуот	573-8	81-0186
SIGNATUR	Et DI.	/	DATE SIGNED	
-	141+TUA		12-8-	10
140 700 19				

.



E.	7
g	5
Ē	0
RIN	A
0	


H20 C Engineering
2401 Tahoe Court
Columbia, MO 65203

573-446-5595 877-22-WATER www.h2oc.com

No.	Date	Bevision	Bv	Designed by: TOC Drawn by: TOC	Vill
				Checked by: JOC Date: November, 2010	тп
					she 1

TITLE SHEET

sheet number 1 of 1



	1	RECEIVED)	
	MISSOURI DEPARTMENT OF NATURAL F WATER PROTECTION PROGRAM, WATE FORM B – APPLICATION FOR CONSTRU FACILITIES WHICH RECEIVE PRIMARILY day) UNDER MISSOURI CLEAN WATER L	R POLLUTION BRANCH 22013 CTION OR OPERATING PERMIT FOR DOMESTIC WASTE (=100,000 gallons p AW	CHE Der DATE	CK NUMBER
NOTE	THE ACCOMPANYING IN	STRUCTIONS BEFORE COMPLETING	HIS FOR	MAND MISERIAN STREET
□ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □	An operating permit and antidegradation revie A construction permit following an appropriate A construction permit and a concurrent operat A construction permit (submitted before Aug. 3 An operating permit for a new or unpermitted for An operating permit renewal: Permit #MO	ew public notice. e operating permit and antidegradation review ting permit and antidegradation review public 30, 2008 or antidegradation review is not re- facility. Construction Permit Expiration Date - MO-0108995 Reason: CONTINATION	ew public lic notice. equired). mit #	notice of the second se
NAME VILLA	GE OF HARTSBURG		TELEPHO	NE WITH AREA CODE
ADDRESS (PHYSICAL)	CITY	STATE	ZIP CODE
POB 24	12011 2202	HARTSBURG	MO	65039
2.2 2.3 .		W ¼, ¼, Sec. 8, T 45, R 12 BOONE withing (Y): lorth referenced to North American Datum 1983 TARY TO SLATE CREEK		
NAME	E OF HARTSBURG	E-MAIL ADDRESS	TELEPHON	E WITH AREA CODE
ADDRESS POB 24	е	CITY HARTSBURG	STATE MO	ZIP CODE 65039
4.	Request review of draft permit prior to Public Not CONTINUING AUTHORITY: Permanent organi maintenance and modernization of the facility	zetion which will person the second	g authorit	
VILLAG	E OF HARTSBURG		TELEPHONE	E WITH AREA CODE
ADDRESS POB 24 5. 0	OPERATOR	CITY HARTSBURG	STATE MO	ZIP CODE 65039
DWAYN	E COOKSEY	CERTIFICATE NUMBER	TELEPHONE	WITH AREA CODE
6. F	ACILITY CONTACT		573-441-	0098
NAME DWAYNI	E COOKSEY	TITLE OPERATIONS MANAGER	TELEPHONE 573-441-	WITH AREA CODE 0098

7.1	ADDITIONAL FACILITY INFORMATION Description of facilities (Attach additional sheet if required). Attach a 1" = 2,000' scale U.S. Geological Survey topographic map showing location of all outfalls and downstream landowners. (See Item 9.)
7.2	Facility SIC code:4952; Discharge SIC code:; Facility NAICS code:; Discharge NAICS code:;
.3	Number of people presently connected or population equivalent (P.E.) 108 Design P.E. 144
	Number of units presently connected: Homes 42 Test
	Design flow for this outfall 14 400 GPD Tatel day of the formation of the
	Commercial Establishment: Doily number of another to a
.4	Length of pipe in the sewer collection system 2 5728 foot/miles (Placed data and the sewer co
5	Length of pipe in the sewer collection system? <u>5728feet/miles</u> (Please denote which unit is appropriate.) Does any bypassing occur in the collection system of at the treatment facility? Does significant infiltration occur in the collection system of at the treatment facility?
6	Does significant infiltration occur in the collection system? \Box Yes \boxtimes No (If yes, attach explanation.) Is industrial waste discharged to the facility identified in less Ω No (If yes, attach explanation and proposed repair.)
7	
В	INVes INVes
	a. Discharge will occur during the following months:
	b. How many days of the week will the discharge occur?
9	is wastewater land applied? Yes XI No. (If yes attach Form L)
10	Will chlorine be added to the effluent?
	a. If chlorine is added, what is the resulting residual? µg/l (micrograms per liter)
1	Does this facility discharge to a losing stream or sinkhole?
∡ 3	
4	Has a waste load allocation study been completed for this facility? List all permit violations, including effluent limit exceedances in the last function and the last function of the last function
-	List all permit violations, including effluent limit exceedances in the last five years. Attach a separate sheet if necessary. If none, write none. LOW MARCH 15, 2007

8.2	Is the sludge a hazardou	S wasto on def	OSAL	こうちょう こうけん からす	a no article sector	and the state of the
0.2	Is the sludge a hazardou Sludge Production include	s waste as den	ined by 10 CSR 25	? 🗌 Yes 🖾 N	lo	and the second second second second
8.3	Sludge Production, include Capacity of sludge holdin	ang sludge rec	erved from others:	2.2 Design Dry 1	ons/Year	Actual Dry Tons/
1000	Sludge storage pr	y structures:	auble feet	1000 000 000 00		
	□ No sludge stora	Ide is provided	cubic feet;	days of storage;	average perc	ent solids of sludge;
8.4	Type of Storage:	Holding t				5-1
		Basin	ank	Building		
	14		Pad	Other (Please	describe)	
8.5	Sludge Treatment:					
	Anaerobic Digester	🗌 Lago	on	Compostin		
	Storage Tank		bic Digester		g ch description)	
	Lime Stabilization	Air or	Heat Drying		ch description)	
8.6	Sludge Use or Disposal:					
	Land Application	🔲 Surfa	ce Disposal (Sludg	e Disposal Lagoon	. Sludge held for m	nore than two years)
	 Contract Hauler Hauled to Another 		i auon			iore than two years)
	Treatment Facility	Sludg	e Retained in Was	tewater treatment la	agoon	
	Solid Waste Landfill	L] Other	Attach exp	planation sheet.	-	
.7	PERSON RESPONSIBLE					
	By Applicant		SLUDGE TO DIS	SPOSAL FACILITY		
AME			ners (complete belo	ow)		
A						
DRESS	-		CITY		STATE	1 1000
NTACT	PERSON			1	STATE	ZIP CODE
			TELEPHONE	WITH AREA CODE	PERMIT	NO.
8	SLUDGE USE OR DISPOS	AL FACILITY			MO-	
	By Applicant	By Others (Please complete b	elow)		
ME A						A
JRESS			0.00			
10.1215.004	PERCON		CITY		STATE	ZIP CODE
10.1275.55	PERSON			/ITH AREA CODE		
NTACT P		diananal	TELEPHONE W		PERMIT	
DRESS	Does the sludge or biosolids	disposal comp	TELEPHONE W		PERMIT	
NTACT P	Does the sludge or biosolids ☐Yes	disposal comp ach explanatio	TELEPHONE W	ge regulations und	PERMIT MO- er 40 CFR 503?	NO.
	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN	disposal comp ach explanatio ER (S). ATTA	TELEPHONE W	ge regulations und	PERMIT MO- er 40 CFR 503?	NO.
E D EDV	Does the sludge or biosolids	disposal comp ach explanatio ER (S), ATTA	TELEPHONE W	ge regulations und	PERMIT MO- er 40 CFR 503?	NO.
E D E D E D E D V RESS	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT	disposal comp ach explanatio ER (S). ATTA	TELEPHONE W oly with federal slud on) CH ADDITIONAL	ge regulations und	PERMIT MO- er 40 CFR 503? SSARY, SEE INS	NO.
NTACT P	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD.	ER (S). ATTA	TELEPHONE W oly with federal slud n) CH ADDITIONAL	ge regulations und	PERMIT MO- er 40 CFR 503?	NO.
E DEDV RESS 11 HA	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY	ER (S) ATTA	TELEPHONE W oly with federal slud n) CH ADDITIONAL S CITY HARTSBU	ge regulations und	PERMIT MO- er 40 CFR 503? SSARY, SEE INS	NO.
E DEDV RESS DI HAJ	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF Y		CITY HARTSBU	ge regulations und SHEETS AS NECE	PERMIT MO- er 40 CFR 503? SSARY, SEE INS	NO.
E D EDV RESS D HAI	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF Y A. Public supply (municipal of If public, please give name	INFORMATIC	CH ADDIMONAL CH ADDIMONAL CH ADDIMONAL CHY HARTSBU	ge regulations und SHEETS AS NECE	PERMIT MO- er 40 CFR 503? SSARY, SEE INS	NO.
E D EDV RESS D HAI	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF A. Public supply (municipal of If public, please give nam B. Private well	INFORMATIC YOUR DRINKI or water district e of the public	CH ADDIMONAL CH ADDIMONAL CH ADDIMONAL CHY HARTSBU	ge regulations und SHEETS AS NECE	PERMIT MO- er 40 CFR 503? SSARY, SEE INS	NO.
E D EDV RESS D HAI	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF Y A. Public supply (municipal of If public, please give nam B. Private well C. Surface water (lake, pond	INFORMATIC YOUR DRINKI or water district e of the public or stream)	TELEPHONE W oly with federal slud n) CH ADDITIONAL S CHY HARTSBU NG WATER SUPP t water) CONSOLI supply	ge regulations und SHEETS AS NECE RG LY: DATED	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. ZIP CODE 65039
E D EDV RESS D HAI	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF Y A. Public supply (municipal of If public, please give nam B. Private well C. Surface water (lake, pond	INFORMATIC YOUR DRINKI or water district e of the public or stream)	TELEPHONE W oly with federal slud n) CH ADDITIONAL S CHY HARTSBU NG WATER SUPP t water) CONSOLI supply	ge regulations und SHEETS AS NECE RG LY: DATED	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. ZIP CODE 65039
E D EDV RESS 1 HAI	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA. Public supply (municipal of If public, please give name S. Private well Surface water (lake, pond Does your drinking water source Yes ☐ No	INFORMATIC YOUR DRINKI or water district e of the public or stream) ce serve at lease	TELEPHONE W oly with federal slud n) CH ADDITIONAL S CITY HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS, ZIP CODE 65039 CONSEcutive days)?
E D EDV RESS D HAA D D D D D O C D D O C D	Does the sludge or biosolids ☐Yes ☐ No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA A. Public supply (municipal of If public, please give name A. Public supply (municipal of MARTING WATER SUPPLY WHAT IS THE SOURCE OF YA A. Public supply (municipal of A. Public supply (municipa	INFORMATIC YOUR DRINKII or water district or stream) ce serve at lease g which is occur ies No	TELEPHONE W Ply with federal slud n) CH ADDITIONAL S CH ADDITIONAL S CHY HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease upied year round b	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year y the same people	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. ZIP CODE 65039 Consecutive days)? clude housing which is
E D EDV RESS D1 HAJ I V A B C C D D O C O C	Does the sludge or biosolids ☐Yes ☐ No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA A. Public supply (municipal of If public, please give name A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of A. Public supply (municipal of A	INFORMATIC YOUR DRINKII or water district or stream) ce serve at lease g which is occur 'es No ne information	TELEPHONE W Ply with federal slud n) CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease upied year round b contained in the ap	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year y the same people	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. ZIP CODE 65039 Consecutive days)? Clude housing which is ledge and belief such
E D EDV RESS D HAA D D D D O C D C D C D C C D C C D C C C C	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN WARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA A. Public supply (municipal of If public, please give name A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of If public, please give name A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of If public, please give name A. Public supply (municipal of If public, please give name A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of MAT IS THE SOURCE OF YA A. Public supply (municipal of A. Public supply (muni	INFORMATIC YOUR DRINKII or water district or stream) ce serve at lease g which is occur 'es No ne information	TELEPHONE W Ply with federal slud n) CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S CH ADDITIONAL S HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease upied year round b contained in the ap	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year y the same people	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. ZIP CODE 65039 Consecutive days)? Clude housing which is ledge and belief such
E D EDV RESS 1 HA 1 V A B C D D C C D C C D C C D C C C C D C	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA. Public supply (municipal of If public, please give nam Private well Surface water (lake, pond Does your drinking water source Yes No Does your supply serve housing coupied seasonally? Y certify that I am familiar with th formation is true, complete an rules, regulations, orders and ater Law NCAL TYLE (TYPE OR BRINT)	ER (S) ATTA	TELEPHONE W Ply with federal slud n) CH ADDITIONAL S CHY HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease upied year round b contained in the ap ad if granted this peo- bject to any legitim	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year y the same people	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO (not necessarily c ? This does not in e best of my know de by the Missouri le to applicant und	NO. TRUCTIONS. 2IP CODE 65039 Consecutive days)? Clude housing which is ledge and belief such Clean Water Law and er the Missouri Clean
E D EDV RESS 1 HA 1 V A B C D D C C D C C D C C D C C C D C C C D C	Does the sludge or biosolids Yes No (Please att DOWNSTREAM LANDOWN VARD JOYCE PICKETT RTSBURG BOTTOM RD. DRINKING WATER SUPPLY WHAT IS THE SOURCE OF YA. Public supply (municipal of If public, please give nam Private well Surface water (lake, pond Does your drinking water source Yes No Does your supply serve housing coupied seasonally? Y certify that I am familiar with th formation is true, complete an rules, regulations, orders and ater Law NCAL TYLE (TYPE OR BRINT)	INFORMATIC YOUR DRINKII or water district or stream) ce serve at lease g which is occur 'es No ne information	TELEPHONE W Ply with federal slud n) CH ADDITIONAL S CHY HARTSBU NG WATER SUPP t water) CONSOLI supply st 25 people at lease upied year round b contained in the ap ad if granted this peo- bject to any legitim	ge regulations und SHEETS AS NECE RG LY: DATED st 60 days per year y the same people	PERMIT MO- er 40 CFR 503? SSARY. SEE INS STATE MO	NO. TRUCTIONS. 2IP CODE 65039 Consecutive days)? Clude housing which is ledge and belief such Clean Water Law and er the Missouri Clean

C

4

6

.

1. Ging of Hondes areg



Boone County Regional Sewer District

1314 North 7th StreetColumbia, Missouri65201-3902(573) 443-2774Fax (573) 499-0489

June 19, 2006

G. Irene Crawford, Regional Director Missouri Department of Natural Resources Northeast Regional Office 1709 Prospect Drive Macon, MO. 63552

RE: Proposed Operating Permit City of Hartsburg - MO 0108995

Dear Ms. Crawford:

The Boone County Regional Sewer District would like to comment on the proposed operating permit for the City of Hartsburg. There is an error on the NPDES Fact Sheet. The District is listed as the owner. Actually, the City of Hartsburg is the owner and the District is the contract operator. In light of these facts it seems that the City of Hartburg should be listed as the "Continuing Authority" on the permit.

Thank you for your attention to this matter.

Yours truly, BOONE COUNTY REGIONAL SEWER DISTRICT

ahra

Tom Ratermann General Manager.

C: File



Boone County Regional Sewer District

1314 North 7th Street Columbia, Missouri 65201-3902 (573) 443-2774 Fax (573) 499-0489

October 22, 2009

Nancy Grant Village of Hartsburg **POB 24** Hartsburg, MO. 65039

RE: Hartsburg wastewater treatment facility permit modification

Dear Ms. Grant,

We have been reviewing our operating permit files and have discovered that the operating permit for the Hartsburg wastewater treatment facility indicates that the District is the continuing authority. Tom Ratermann sent a letter to the Missouri Department of Natural Resources with regards to this error on June 19, 2006. We have found that in order to change this on the permit a modification to the permit must be applied for. I have completed the application for you to send to MDNR. You will need to send the MDNR the application along with a check in the amount of \$ 200.00 for the modification fee. I will keep a copy of application in our permit file. I apologize for the inconvenience. If you have any questions give me a call at 573-441-0098.

Sincerely, mé Coo

Operations Manager

C: Tom Ratermann File